Debris Pile Removal Design

Former Markwardt Brothers Garage West Chocktoot Street & North 1st Avenue Chiloquin, Klamath County, Oregon

Prepared for: City of Chiloquin EPA Cooperative Agreement #BF-02J00701 February 25, 2022





now



Contact Information

Cardno Inc., now Stantec 6611 Bay Circle Suite 220 Norcross, Georgia 30071, USA Telephone: +1 (678) 433 1197 www.cardno.com www.stantec.com

Document Information

Prepared for

City of Chiloquin P.O. Box 196 Chiloquin, Oregon 97624

Project Name

Debris Pile Removal Design West Chocktoot Street Chiloquin, OR

Cardno Project# CHILOQ300 EPA ACRES# 250932 Date February 2022

Document History

Version	Effective Date	Description of Revision	Prepared by	Reviewed by
1.0	2/25/2022	Original Document	Robert Hall, P.G.	Keith Ziobron, P.E.

This document is produced by Cardno solely for the benefit and use by the client in accordance with the terms of the engagement. Cardno does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by any third party on the content of this document.

Table of Contents

1			ackground	1
	1.1	Site De	escription	1
	1.2		g History and Property Description	1
	1.3		us Environmental Assessments	1
	1.4	Davis-E	Bacon Act	2
2	Scop	e of Work		3
	2.1	Execut	ion Plan	3
	2.2	Health	and Safety Plan	4
	2.3	Training	g	4
	2.4	Permits	s and Notifications	5
	2.5	Mobiliz	ation and Site Preparation	5
	2.6	Asbest	os-Containing Materials	5
	2.7	Demob	ilization	5
3	Asbe	stos Abat	ement Specification	6
	3.1	Part 1 -	– General	6
		3.1.1	Introduction	6
		3.1.2	References	6
		3.1.3	Definitions	8
		3.1.4	Contractor Responsibilities	12
		3.1.5	Owner Responsibilities	13
		3.1.6	Job Conditions	13
		3.1.7	Personnel	15
		3.1.8	Emergency Planning	15
		3.1.9	Authority to Stop Work	16
		3.1.10	Agreement to Pay Fines	16
		3.1.11	Hold Harmless Agreement	16
	3.2	Part 2 -	 Procedures Prior to Starting Abatement 	16
		3.2.1	Post Warning Signs and Establish Regulated Area	16
		3.2.2	Decontamination Facilities	16
		3.2.3	Segregation of Work Areas – Gross Removal Areas	17
		3.2.4	Preparation of Work Area for Abatement	17
		3.2.5	Isolation and Shutdown of Building HVAC System	18
		3.2.6	Negative Pressure Establishment and Maintenance	18
	3.3	Part 3 -	 Procedures for Friable Asbestos Abatement 	18
		3.3.1	Entry and Exit from Work Area	18
		3.3.2	Respiratory Protection during Asbestos Removal	19
		3.3.3	Work Practices	19
		3.3.4	Asbestos Removal Procedures – General	19
		3.3.5	Asbestos Removal Procedures – Detailed	20
		3.3.6	Clean Up Procedures	20

	Air Monitoring	20
3.3.8	Disposal of Asbestos Waste	21
References		23

Bid Form

4

Contractor Bid Form

Tables

- 1 Summary of ACM Bulk Sample Results
- 2 Summary of Lead Waste Characterization Results

Figures

- 1 ACM Sample Location Map
- 2 TCLP Lead Sample Location Map

Appendices

- A Photo Log
- B Laboratory Reports Cardno April 2021 Sampling Event
- C Asbestos Inspector and Project Designer Certificates

1 Introduction/Background

This Environmental Abatement Design (Design) has been prepared for the Former Markwardt Brothers Garage property located at the northeast corner of West Chocktoot Street and North 1st Avenue, in Chiloquin, Klamath County, Oregon (site) to programmatically ready the site for redevelopment. This project details the removal of a construction and demolition (C&D) debris pile from the collapsed former Chiloquin Mercantile that is contaminated with asbestos-containing materials (ACM). The scope of work detailed in this Design will be initiated upon procurement of an asbestos abatement contractor (Contractor), which is expected to occur in March 2022.

This Design was prepared to procure competitive bids from asbestos abatement contractors for equivalent work to be completed. In addition, this Design provides an asbestos abatement specification in accordance with the EPA Asbestos National Emission Standards for Hazardous Air Pollutants (NESHAP) and Toxic Substances and Control Act (TSCA).

1.1 Site Description

According to the Klamath County Tax Assessors office, the site consists of two tax parcels totaling approximately 0.55-acres, identified by tax parcel identification numbers 3407-034DC-00500 and 3407-034DC-00400. The parcels are situated along North 1st Avenue and West Chocktoot Street, and consist of undeveloped land (north parcel) and a single-story approximately 8,500 square-feet former automotive garage/service station, and the subject debris pile. The site layout is provided on **Figure 1**.

1.2 Building History and Property Description

According to the City of Chiloquin Public Works Department, the automotive garage operated as an auto repair/car dealership and gasoline service station from the 1930s through the 1960s; a second-hand store in the 1970s; and the Juniper Wood Products facility in the 1980s. A commercial building formerly occupied by the Chiloquin Mercantile adjoined the garage's north wall until it collapsed due to structural failure in approximately 2018. The remnants of this building are the subject C&D debris pile. The area to the north of the debris pile consists of vacant land that was once occupied by a rooming house.

The surrounding area is primarily developed with commercial buildings associated with downtown Chiloquin. Photos of the site and debris pile are provided in **Appendix A**.

1.3 Previous Environmental Assessments

The following investigations, assessments, and/or applications have been completed at the site:

- Phase I Environmental Site Assessment (ESA), Cardno, May 2021
- Asbestos and Lead-Based Paint Survey, Cardno, May 2021
- Oregon Department of Environmental Quality (ODEQ) Voluntary Cleanup Program Application, Cardno, June 2021 (ODEQ approval)
- Phase II ESA and Debris Pile Sampling, Cardno, August 2021
- Updated Phase I ESA, Cardno, November 2021

Valuable information was collected during the execution and preparation of the previous environmental assessments; however, this design focuses on the results of the Phase II ESA as presented in the Debris Pile Sampling report (Cardno, August 2021) that included the collection and analysis of asbestos and lead toxicity characteristic leachate procedure (TCLP) samples.

Asbestos:

There were 6 bulk material samples collected from 3 homogenous areas analyzed for asbestos. Sample locations are provided on **Figure 1**. The two drywall samples collected were split by the laboratory into applicable layers and found to contain 2 percent chrysotile asbestos. Due to the nature of the debris pile, the ACM cannot be completely segregated from the pile, therefore the entire pile must be treated as an asbestos-contaminated material and subject to asbestos abatement regulations. The asbestos laboratory report is provided in **Appendix B**.

Lead:

There were 2 composite samples collected from the debris pile and analyzed for lead via TCLP for waste characterization purposes. Sample locations are provided on **Figure 2**. The results were below the reporting limit for lead. The asbestos laboratory report is provided in **Appendix B**.

1.4 Davis-Bacon Act

All abatement work is expected to be partially funded by federal funds and therefore must comply with the Davis-Bacon Act (DBA) which requires payment of the prevailing wage rate for cleanup activities. The budget and schedule must take this into account. More details regarding the DBA can be found on the US Department of Labor's (DOL) website: https://www.dol.gov/whd/regs/compliance/whdfs66.pdf.

Additionally, work conducted under Business Oregon contracts must also comply with State labor standards and wage rates found in Oregon Revised Statutes (ORS) Chapter 279C.

Note: The contractor's bid must affirm that the bid has been developed and the work completed upon award will comply with all conditions of the Davis-Bacon Act and ORS Chapter 279C

2 Scope of Work

The Contractor will perform the following tasks as part of the Scope of Work:

- Prepare a general Execution Plan and Site-Specific Health and Safety Plan (HASP) for review and approval. Establish decontamination stations for personnel and vehicles, traffic patterns, staging areas, and a waste management plan for review and approval.
- Prepare all regulatory agency notifications, permits, and compliance documentation required to facilitate the work.
- Remove, containerize, transport, and dispose of the asbestos-contaminated debris pile. The extent of the confirmed asbestos-contaminated debris pile is shown on **Figure 1**. The debris pile consists of all remnant building debris (brick, mortar, glass, drywall/joint compound, plaster, wood, roofing materials, and etc).
- Final cleaning of the underlying concrete slab must be completed to remove any potential residual ACM. Visually confirm that all debris and residual material has been removed from the remaining concrete slab or underlying soil where concrete slab is not present. Any depressions observed in the concrete slab or underlying soil must be backfilled with #57 stone or equivalent and appropriately compacted.
- It is assumed that that duration of this project will be short and only a final closure report will be required. A final closure report will be provided by the contractor that includes all of the waste documentation and certification that all regulated and/or specified materials have been removed from the site.

2.1 Execution Plan

The following information is required to be submitted as part of the Contractor's Execution Plan submittal:

- Within 10 business days of the Contractor's Agreement execution, a detailed Execution Plan that describes how the Contractor proposes to conduct the requested work activities must be submitted to the Owner and the Owner's Representative.
 - Owner Teresa Foreman: Chicityhall@gmail.com
 - Owner's Representative Keith Ziobron and Robert Hall: keith.ziobron@cardno.com and Robert.m.hall@cardno.com
- The Execution Plan must, at a minimum, include the following:
 - o Identification of all personnel, equipment, and materials to be used.
 - Identification of all subcontractors (if any) to be used and their role in conducting elements of the Work. Owner's Representative must give written approval of all subcontractors prior to their entering the facility.
 - Truck traffic routes, staging areas, personnel decontamination stations, and parking areas for Site personnel.

- Proposed waste management approach (including collection, segregation, and containerization of wastes, transportation & disposal for all waste, and which disposal facility to be used)
- Proposed execution schedule showing the work days and hours within 6:00 a.m. 6:00 p.m., Monday – Friday (unless otherwise approved by the Owner).
- Provide names and resumes of its nominated key personnel (such as, but not limited to, Project Manager, Site Supervisor, and Site Health and Safety Officer) for Owner's Representative acceptance.

2.2 Health and Safety Plan

Contractor must prepare a site-specific HASP in accordance with OSHA requirements as specified in Code of Federal Regulations (CFR) Title 40 Part 1910.120 and 29 CFR 1926, as applicable, as well as Construction Safety 29 CFR Part 1926 – OSHA General Construction Standards and 29 CFR Part 1926 Subpart T – Standards for Demolition Activities.

Contractor must provide the HASP to the Owner's Representative for review at least five days prior to Contractor's mobilization. All site-specific HASPs must be adhered to during the work and include the personal protective equipment (PPE) required to safely perform the work. PPE will at a minimum include the following: protective clothing, respirator (when required), safety toe shoes, long pants, high-visibility (reflective) vest or garment, safety glasses with side shields, and a hard hat. Other tasks may warrant additional PPE such as cut-resistant gloves, hearing protection, and respiratory protection. The HASP will detail worker protection and monitoring measures for the regulated constituents present on Site.

Prior to beginning any work, Contractor will provide a health and safety orientation to personnel working on the project. The purpose of the orientation will be to confirm that site personnel have a firm understanding of the project hazards and the administrative and/or engineered controls implemented to control these hazards.

At the start of each work day and after lunch prior to re-initiation of work, each Contractor will participate in a tailgate safety meeting. The meeting will be attended by all Contractor and subcontractor personnel working at the site as well as an Owner's representative. The health and safety meetings will be effective in reinforcing the concepts presented in the HASP, helping personnel stay focused on implementing safe work practices, and be documented by a tailgate safety form signed by all personnel in attendance.

In addition to the above requirements, personnel must abide by site-specific safety rules and procedures, such as obtaining relevant work permits, non-smoking requirements, and drug-free workplace requirements.

2.3 Training

All onsite personnel involved in handling/removal of regulated (or potentially regulated) materials must have, at a minimum, OSHA 40-hour Hazardous Waste Training (29 CFR 1910.120 and 1926.65) with the corresponding annual 8-hour refresher courses and be a DEQ-licensed asbestos abatement contractor. Copies of relevant individual training certificates are required to be on-site during abatement activities.

2.4 **Permits and Notifications**

Upon notice to proceed and prior to mobilization, the Contractor will prepare and secure the applicable permits, licenses, and notifications necessary for executing the asbestos abatement, cleaning, and demolition tasks. In addition to the Federal (NESHAP notification) and State of Oregon (ASN-1) requirements, the site is located within the City limits of Chiloquin and may require local permits or notifications. The Contractor is required to submit draft applications/notifications to the Owner's Representative for review and approval at least 3 days prior to submittal to any regulatory authority. A copy of the finalized documentation must be present during operations.

2.5 Mobilization and Site Preparation

Various mobilization activities must be completed prior to initiating the work. These activities aid in preparing and maintaining a safe site and are paramount to the successful completion of any project. These activities will include, but not be limited to:

- Mobilize the necessary personnel, equipment, supplies, materials, and resources to the site to perform the work;
- Conduct a pre-construction meeting at the site prior to beginning work;
- Delineate work zones, including posting necessary signs, warning tape, etc.; and
- Set up staging areas for equipment and supplies as necessary.
- Mobilize decontamination stations and sanitary facilities for workers and institute measures to prevent tracking out of any regulated material residue from the site.

2.6 Asbestos-Containing Materials

Cardno conducted a debris pile sampling event at the site in August 2020. Asbestos containing drywall and joint compound materials were identified mixed into the debris pile and is unable to be segregated from the rest of the debris. As such, the debris pile is considered to be asbestos-contaminated and must be removed. **Figure 1** provides the general location of the debris pile to be removed. The ACM summarized below are also provided in the attached **Bid Form**.

• Asbestos-contaminated C&D debris pile: 450 Cubic Yards (CY)

A detailed specification for the removal of ACM was prepared by Mr. Robert Hall of Cardno and is provided as **Section 3** of this Design. Mr. William Smithwick collected the asbestos bulk samples and a copy of his asbestos inspector certification is provided in **Appendix C**. A copy of Mr. Hall's Asbestos Project Designer Certification is also provided in **Appendix C**.

2.7 Demobilization

Following the abatement, the contractor shall visually confirm that all debris and residual materials have been removed from the concrete slab or underlying soil within the footprint of the debris pile. Any observed depressions must be backfilled with #57 stone or equivalent and appropriately compacted.

Upon completion of project activities to Owner's Representative approval, the Contractor will promptly demobilize equipment, tools, and personnel from the site. Equipment and tools will be decontaminated as necessary prior to leaving the site. Personnel and vehicle decontamination stations will be properly cleaned and decommissioned. PPE and all wastes will be properly characterized, containerized, transported and disposed, as other wastes.

3 Asbestos Abatement Specification

3.1 Part 1 – General

3.1.1 <u>Introduction</u>

A. Description of Work

The following ACM have been identified by Cardno. All of these materials are to be removed as part of this environmental abatement project.

HA Name	Quantity/Area	Location
ACM-Contaminated Debris	450 CY	Exterior North of Structure

B. Abatement Methods

Methods of abatement are to be specified by the Contractor in their execution plan and approved of by the Owner's Representative. It is assumed that the entire abatement will be completed using heavy equipment under outdoor project techniques and best practices.

3.1.2 <u>References</u>

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

AMERICAN NATIONAL STANDARDS INSTITUTE (ANSI)

ANSI Z9.2 (1979; R 1991) Fundamentals Governing the Design and Operation of Local Exhaust Systems

ANSI Z87.1 (1989; Errata; Z87.1a) Occupational and Educational Eye and Face Protection

ANSI Z88.2 (1992) Respiratory Protection

AMERICAN SOCIETY FOR TESTING AND MATERIALS (ASTM)

ASTM C 732 (1982; R 1987) Aging Effects of Artificial Weathering on Latex Sealant

ASTM D 522 (1992) Mandrel Bend Test of Attached Organic Coatings

ASTM D 1331 (1989) Surface and Interfacial Tension of Solutions of Surface-Active Agents

ASTM D 2794 (1990) Resistance of Organic Coatings to the Effects of Rapid Deformation (Impact)

ASTM D 4397 (1991) Polyethylene Sheeting for Construction, Industrial, and Agricultural Application

ASTM E 84 (1991A) Surface Burning Characteristics of Building Materials

ASTM E 96 (1993) Water Vapor Transmission of Materials

ASTM E 119 (1988) Fire Tests of Building Construction and Materials

ASTM E 736 (1986; R 1991) Cohesion/Adhesion of Sprayed Fire-Resistive Materials applied to Structural Members

ASTM E 1368 (1990) Visual Inspection of Asbestos Abatement Projects

CODE OF FEDERAL REGULATIONS (CFR)

CFR 29 Part 1910.1101 Occupational Safety and Health Standards

CFR 29 Part 1926 Safety and Health Regulations for Construction

CFR 40 Part 61 National Emission Standards for Hazardous Air Pollutants

CFR 40 Part 763 Asbestos

COMPRESSED GAS ASSOCIATION (CGA)

CGA G-7(1990) Compressed Air for Human Respiration

CFA G-7.1 (1989) Commodity Specification for Air

ENVIRONMENTAL PROTECTION AGENCY (EPA)

EPA 340/1-90-018 (1990) Asbestos/NESHAP Regulated Asbestos Containing Materials Guidance

EPA 340/1-90-019 (1990) Asbestos/NESHAP Adequately Wet Guidance

EPA 560/5-85-024 (1985) Guidance for Controlling Asbestos Containing Materials in Building

NATIONAL FIRE PROTECTION ASSOCIATION (NFPA)

NFPA 10 (1990) Portable Fire Extinguishers

NFPA 70 (1993) National Electrical Code

NFPA 90A (1993) Installation of Air Conditioning and Ventilating Systems

NFPA 101 (1994) Safety to Life from Fire in Buildings and Structures

NFPA 701(1989) Methods of Fire Test for Flame-Resistance Textiles and Films

NATIONAL INSTITUTE FOR OCCUPATIONAL SAFETY AND HEALTH (NIOSH)

NIOSH Pub No. 84-100 (9184; Supple 1985, 1987, 1988, 1990) NIOSH Manual of Analytical Methods

OREGON DEPARTMENT OF ENVIRONMENTAL QUALITY

OREGON ADMINISTRATIVE RULES 340, DIVISION 248

UNDERWRITERS LABORATORIES (UL)

UL 586 (1990) High-Efficiency, Particulate, Air Filter Unit

3.1.3 <u>Definitions</u>

- 1. Abatement Removal and proper disposal of asbestos-containing materials.
- 2. ACGIH American Conference of Governmental Industrial Hygienists.
- 3. Adequately Wet A term as defined in -CFR 40 Part 61-, Subpart M and -EPA 340/1-90-019-that means to sufficiently mix or penetrate with liquid to prevent the release of particulates. If visible emissions are observed coming from ACM, then that material has not been adequately wetted. However, the absence of visible emissions is not sufficient evidence of being adequately wetted.
- 4. AIHA American Industrial Hygiene Association.
- 5. Air lock A system for permitting ingress and egress with minimum air movement between a contaminated area and uncontaminated area, typically consisting of two curtained doorways separated by a distance of at least 3 feet such that one passes through doorway into the air lock, allowing the doorway sheeting to overlap and close off the opening before proceeding through the second doorway, thereby preventing flow-through contamination.
- 6. Air Monitoring The process of measuring the fiber content of a known volume of air collected during a specific period of time. The procedure normally utilized for asbestos follows the NIOSH Method 7400. For clearance air monitoring, Transmission Electron Microscopy (TEM) methods when required, by the AHERA regulations will be used.
- 7. Air Sampling Professional The professional contracted or employed by the Building Owner to supervise and/or conduct air monitoring and analysis schemes. This individual may also function as the Asbestos Consultant if qualified.
- 8. Amended Water Water containing a wetting agent or surfactant with a surface tension of at least 29 dynes per square centimeter when tested in accordance with ASTM 01331.
- 9. ANSI American National Standards Institute.
- 10. Asbestos the asbestiform varieties of serpentine (chrysotile), riebeckite (crocidolite), cummingtonite grunerite (amosite), anthophyllite, actinolite, and tremolite.
- 11. Asbestos-Containing Material (ACM) Material composed of asbestos of any type and in an amount greater than 1% by weight, either alone or mixed with other fibrous or non-fibrous materials.
- 12. Asbestos-Containing Waste Material asbestos containing material or asbestos contaminated objects requiring disposal.
- 13. Asbestos Consultant An individual qualified by virtue of experience and education, designated as the Owner's representative and responsible for overseeing the asbestos abatement project.
- 14. Asbestos Fibers Asbestos fibers having an aspect ratio of at least 3:1 and 5 micrometers or longer in length.
- 15. ASTM American Society for Testing and Materials.
- 16. Authorized visitor The Owner (and any designated representatives) and any representative of the regulatory or other agency having jurisdiction over the project.

- 17. Owner The Owner or his authorized representative.
- 18. Category I Non-friable ACM A term as defined in CFR Part 61 Subpart M and EPA 340/1-90-018 that means asbestos-containing packing, gasket, resilient floor covering, and asphalt roofing products containing more than 1 percent asbestos as determined using the method specified in CFR 40 Part 763, Appendix A, Subpart F, Section 1, Polarized Light Microscopy.
- Category II Non-friable ACM A term as defined in CFR Part 61 Subpart M and EPA 340/1-90-018 that means any non-friable ACM material, excluding Category I non-friable ACM, containing more than 1 percent asbestos as determined using the methods specified in Category I Nonfriable ACM.
- 20. Certified Industrial Hygienist (CIH) An industrial hygienist certified in Comprehensive Practice by the American Board of Industrial Hygiene.
- 21. Class I Asbestos Work (29 CFR 1926.1101) Means activities involving the removal of TSI and Surfacing ACM and PACM.
- 22. Class II Asbestos Work (29 CFR 1926.1101) Means activities involving the removal of ACM which is not thermal system insulation or surfacing material. This includes, but is not limited to the removal of asbestos-containing wallboard, floor tile and sheeting, roofing and siding shingles and constructions mastics.
- 23. Clean Room An uncontaminated area or room which is a part of the worker decontamination enclosure system with provisions for storage of worker's street clothes and clean protective equipment.
- 24. Contractor The individual and/or business with which the Building Owner arranges to perform the asbestos abatement. It is recommended that wherever asbestos abatement is part of a larger project, the asbestos work be contracted separately and distinctly from other contract work. When this is not possible, the Contractor is responsible for the proper completion of project activities in accordance with this contract specification even where a subcontractor has been retained to perform the actual abatement.
- 25. Curtained doorway A device to allow ingress or egress from one room to another while permitting minimal air movement between the rooms, typically constructed by placing two overlapping sheets of plastic over an existing or temporarily framed doorway securing each along the top of the doorway, securing the vertical edge of one sheet along one vertical side of the doorway and securing the vertical edge of the other sheet along the opposite vertical side of the doorway. Other effective designs are permissible.
- 26. Decontamination enclosure system A series of connected rooms, separated from the work area and from each other by air locks, for the decontamination of workers and equipment.
- 27. Demolition The wrecking or taking out of any load-supporting structural member of a facility together with any related handling operations.
- 28. Encapsulant A liquid material which can be applied to asbestos-containing material which controls the possible release of asbestos fibers from the material either by creating a membrane over the surface (bridging encapsulant) components together (penetrating encapsulant).

- 29. Encapsulation The application of an encapsulant to control the release of asbestos fibers into the air.
- 30. Enclosure The construction of an air-tight, impermeable, permanent barrier around asbestos containing material to control the release of asbestos fibers into the air.
- 31. EPA Environmental Protective Agency.
- 32. Equipment decontamination enclosure system That portion of a decontamination enclosure system designed for controlled transfer of materials and equipment into or out of the work area, typically consisting of a washroom and holding area.
- 33. Equipment room A contaminated area or room which is part of the worker decontamination enclosure system with provisions for storage of contaminated clothing and equipment.
- 34. Facility Any institutional, commercial or industrial structure, installation, or building.
- 35. Facility component Any pipe, duct, boiler, tank, reactor, turbine, or furnace at or in a facility or any structural member of a facility.
- 36. Fibers All fibers regardless of composition as counted in the NIOSH 7400 procedure.
- 37. Fixed object A piece of equipment or furniture in the work area which cannot be removed from work area.
- 38. Friable ACM A term as defined in CFR 40 Part 61, Subpart M and EPA 340/1-90-018 that means any material containing more than 1 percent asbestos as determined using the method specified in CFR 40 Part 763, Appendix A, Subpart F, Section 1, Polarized Light Microscopy, that when dry, can be crumbled, pulverized, or reduced to powder by hand pressure.
- 39. Glovebag technique A method with limited applications for removing small amounts of friable asbestos containing material from HVAC ducts, short piping runs, valves, joints, elbows, and other non-planar surfaces in a non-contained (plasticized) work area. The glovebag assembly is a manufactured or fabricated device consisting of a 6-mil transparent polyethylene or polyvinylchloride plastic bag with two inward projecting long-sleeves and an internal tool pouch.

The glovebag is constructed and installed in such a manner that it surrounds the object or material to be removed and contains all asbestos fibers released during the process. All workers who are permitted to use the glovebag technique must be highly trained, experienced, and skilled in this method.

- 40. HVAC heating, ventilation, and air conditioning system.
- 41. HEPA filter A high efficiency particulate air filter capable of removing particles as small as 0.3 microns in diameter with 99.97% efficiency.
- 42. HEPA vacuum A vacuum system equipped with HEPA filtration.
- 43. Holding area A chamber in the equipment decontamination enclosure located between the washroom and an uncontaminated area.
- 44. Movable object A piece of equipment or furniture in the work area which can be removed from

the work area.

- 45. Negative pressure ventilation system a portable exhaust system equipped with HEPA filtration and capable of maintaining a constant low velocity air flow from contaminated areas into adjacent uncontaminated areas post-filtration.
- 46. NESHAP The National Emission Standard for Hazardous Air Pollutants (40 CFR Part 61).
- 47. NIOSH The National Institute for Occupational Safety and Health.
- 48. Non-friable ACM A term as defined in CFR Part 61 Subpart M and EPA 340/1-90-018 that means any material containing more than 1 percent asbestos as determined using the method specified in CFR 40 Part 763, Appendix A, Subpart F, Section 1, Polarized Light Microscopy, that, when dry, cannot be crumbled, pulverized or reduced to powder by hand pressure.
- 49. OSHA The Occupational Safety and Health Administration.
- 50. Outside air The air outside buildings and structures.
- 51. Plasticize (polyethylene) To cover floors and walls with plastic sheeting as herein specified.
- 52. Prior experience Experience required of the contractor on asbestos projects of similar nature and scope to insure capability of performing the asbestos abatement in a satisfactory manner. Similarities will be in areas related to material composition, project size, abatement methods required, number of employees and the engineering, work practice and personal protection controls required.
- 53. Removal The stripping of any asbestos-containing materials from surfaces or components of a facility.
- 54. Renovation Altering of facility components. Operations in which load-supporting structural members are wrecked or taken out are excluded.
- 55. Shower room A room between the clean room and the equipment room in the worker decontamination enclosure with hot and cold or warm running water controllable at the tap and suitably arranged for complete showering during decontamination.
- 56. Staging area Either the holding area or some area near the waste transfer air lock where containerized asbestos waste has been placed prior to removal from the work area.
- 57. Strip To remove asbestos materials from any part of facility.
- 58. Structural member Any load-supporting member of a facility, such as beams and load-supporting walls or any non-load-supporting member, such as ceilings and non-load supporting walls.
- 59. Surfactant A chemical wetting agent added to water to improve penetration.
- 60. Time-Weighted Average (TWA) The TWA is an 8-hour time weighted average of airborne concentration of fibers (longer than 5 micrometers) per cubic centimeter of air which represents the employee's 8-hour workday as determined by Appendix A of CFR 29 Part 1926.1101.
- 61. Visible emissions Any emissions that are visually detectable without the aid of instruments. This does not include condensed uncombined water vapor.

- 62. Waste transfer air lock A decontamination system utilized for transferring containerized waste from inside to outside of the work area.
- 63. Wet cleaning The process of eliminating asbestos contamination from building surfaces and objects by using cloths, mops, or other cleaning utensils which have been dampened with amended water and afterwards thoroughly decontaminated or disposed of as asbestos contaminated waste.
- 64. Work area Designated rooms, spaces, or areas of the project in which asbestos abatement actions are to be undertaken or which may become contaminated as a result of such abatement actions. A contained work area is a work area which has been sealed, plasticized, and equipped with a decontamination enclosure system. A non-contained work area is an isolated or controlled-access work area which has not been plasticized nor equipped with a decontamination enclosure system.
- 65. Worker decontamination enclosure A decontamination system consisting of a clean room, a shower room, and an equipment room separated from each other and from the work area air locks and contained doorways.

3.1.4 <u>Contractor Responsibilities</u>

A. General

The Contractor shall assume full responsibility and liability for compliance with all applicable Federal, State, and local regulations pertaining to work practices, preparation for hauling, protection of workers, visitors to the site, and persons occupying areas adjacent to the site. The Contractor is responsible for providing medical examinations and maintaining medical records of personnel as required by the applicable Federal, State, and local regulations. The Contractor shall hold the Owner and Owner's Representative harmless for failure to comply with any applicable work, hauling, disposal, safety, health, or other regulation on the part of himself, his employees, or his subcontractors.

B. Training/Licensing

The Contractor shall insure that all employees of the Contractor who will be performing asbestos removal activities have been provided with training that meets or exceeds the requirements found in the applicable OSHA standards, especially the standard for asbestos (29 CFR 1926.1101). A copy of all required business licenses, training certificates, and personal licenses must be kept on site at all times during work activities.

Additionally, all workers must comply with specific training that may be required by the general contractor.

C. Medical Requirements

The Contractor shall ensure that all employees of the Contractor who will be performing asbestos removal activities will have been provided with a medical examination that meets or exceeds the requirements found in the applicable OSHA standards, especially the standard for asbestos (29 CFR 1926.1101). Further, the Contractor shall insure that all medical records developed pursuant to the above requirements will be maintained according to the applicable OSHA standards, especially the standards, especially the standard for asbestos (29 CFR 1926.1101).

D. Respiratory Protection Program

The Contractor shall establish and maintain an effective respiratory protection program that meets or exceeds the requirements found in the applicable OSHA standards, especially the standard for asbestos (29 CFR 1926.1101) and the standard for Respiratory Protection (29 CFR 1910.114).

E. Regulatory Compliance

The Contractor shall comply with all applicable environmental, health and safety regulations as promulgated by appropriate Federal, State or local regulatory authority. In particular, the Contractor is required to comply with all sections of the OSHA standard for Occupational Exposure to Asbestos as found in 29 CFR 1926.1101; and the NESHAP regulations as found in 40 CFR Part 61.

F. Notice to Asbestos Consultant

The Contractor is required to provide at least 24-hour notice to the Asbestos Consultant to allow for the following:

- 1. Inspection of the work area prior to beginning removal of ACM.
- 2. Final visual inspection.
- G. Notice to Regulatory Agencies

A permit application and notification must be prepared for this project and submitted by the Contractor to the Oregon Department of Environmental Quality. Remediation work will not begin until at least 10 days after the submission date.

H. Electrical Requirements

The Contractor is responsible for all electrical requirements needed to perform the work as described in the specifications. All the Contractor's electrical equipment must be connected to a ground fault protected panel.

- I. Abatement Area Security
 - 1. The work area is restricted to authorized, trained, and protected personnel. These may include the Contractor's employees, employees of Subcontractors, Owner's employees and representatives, state and local inspectors and any other designated individuals. A list of authorized personnel must be established prior to job start.
 - 2. Entry into the work area by unauthorized individuals will be reported immediately to the Asbestos Consultant by the Contractor.
 - 3. A sign-in log must be maintained by the asbestos project supervisor. Anyone who enters the work area must record name, affiliation, time in, and time out for each entry.
 - 4. Access to the work area will be through a single point in the demarcation area. The only exception for this rule is in the event of an emergency, such as fire or accident.
 - 5. The Contractor shall provide work area security during abatement operations.

3.1.5 <u>Owner Responsibilities</u>

It is the responsibility of the Owner to provide the following:

1. Access to the work area at the scheduled work times and such other times as mutually agreed upon.

3.1.6 Job Conditions

A. Conditions of Work Area

The Owner assumes no responsibility for the actual condition of the work area.

B. Damage

Work will be completed within and adjacent to historic structures. The contractor must exercise care so as not to damage or otherwise harm the historic integrity of the Site structures.

C. Utilities

The Contractor shall make arrangements for all water, electricity, and other utilities necessary in the area of operations. The Contractor shall provide his own temporary lighting in the area of operations, if required.

D. Safety

Ensure safe passage of persons around area of abatement. Conduct operations to prevent injury or damage to facilities and persons. Local medical emergency personnel, both ambulance crews and hospital emergency room staff, must be notified as to the possibility of having to handle contaminated, injured persons and be advised on safe decontamination procedures.

E. Security

The Contractor shall secure the demarcated work area to keep unauthorized personnel from accidentally entering the area in which asbestos is being removed.

F. Containment Log

The Contractor shall maintain a log of entry to the demarcated area. The log must be signed by every person that enters the secured area. A copy of this log will be made available to the Asbestos Consultant for all on-site visits.

G. Visitor Protection

All persons entering the work area must wear PPE required for the Site and the work area. There will be no exceptions to this requirement.

H. Daily Report

The Contractor shall maintain for the benefit of the Owner, a daily report which must include, but not be limited to, hours of work, size of crew, work type and progress, special conditions encountered, and any other information appropriate to fully describe the job conditions.

I. Contractor Representative

The Contractor shall name an individual at the job site who will be in charge of the Contractor's activities on the job site. The individual named will be the principal point of contact on the job site for representatives of the Owner and the Asbestos Consultant and will be empowered to take corrective actions if activities are found to be in violation of the specification. The individual must remain at the job site as long as any aspect of the work required is in progress.

J. Storage of Equipment and Supplies

Storage of Contractor equipment must meet the approval of the Owner and the Asbestos Consultant

- K. Contractor Use of Premises
- 1. The Contractor will limit his use of the premises to the work indicated and confine operations to

the areas permitted under the Contract. Portions of the site beyond areas on which work is indicated are not to be disturbed.

- 2. Do not unreasonably encumber the site with materials or equipment. Confine stockpiling of materials to the approved areas.
- 3. Keep existing driveways and entrances serving the premises clean and available to the Owner at all times. Do not use these areas for parking or storage of materials.
- 4. Lock automotive type vehicles, such as passenger cars and trucks and other mechanized or motorized construction equipment, when parked and unattended, so as to prevent unauthorized use.
- 5. Maintain existing area in a safe condition throughout operations.

3.1.7 <u>Personnel</u>

A. General Superintendent:

Provide a full-time General Superintendent who is experienced in administration and supervision of asbestos abatement projects including work practices, protective measures for environment and personnel, disposal procedures, etc. This person is the Competent Person and is the Contractor's representative, responsible for compliance with all applicable Federal, State, and local regulations, particularly those relating to asbestos-containing materials. This person must have completed a course at an EPA Training Center or equivalent certificate course in asbestos abatement procedures, have had a minimum of five years on-the-job training and meet any additional requirements set forth in 29 CFR 1926 for a Competent Person. In addition, the Contractor shall have a Oregon accredited Supervisor present whenever abatement or waste loading operations is taking place. The superintendent may act as the supervisor.

B. Competence of Workmen

If any employee of the Contractor, in the opinion of the Owner or the Asbestos Consultant is careless in the execution of the work or is otherwise objectionable or unacceptable in his performance must be removed upon request of the Owner, Asbestos Consultant, or their representative.

C. Crews

The Contractor shall provide work crews in sufficient numbers to complete all asbestos removal operations according to the agreed upon schedule.

D. Conduct of Workmen

No alcoholic beverages or drugs will be permitted on Site grounds. All soft drink bottles, wrappers, etc., are to be removed each day. This work site will also be non-smoking, with the exception of a designated and approved smoking area. All debris and waste from smoking must be removed on a daily basis.

3.1.8 <u>Emergency Planning</u>

The Contractor shall adhere to the existing health and safety plan and emergency action plan at all times while on site. Emergency planning must include considerations of fire, explosion, toxic atmospheres, electrical hazards, slips, trips and falls, confined spaces and weather/temperature related injury. Written procedures and employee training in procedures must be provided.

Employees will be trained in evacuation procedures in the event of a workplace emergency.

1. For non-life-threatening situations, employees injured must decontaminate following normal procedures with assistance from fellow workers if necessary before exiting the workplace to obtain proper medical treatment.

2. For life-threatening injury or illness, worker decontamination will take least priority after measures to stabilize the injured worker, remove him from the workplace and secure proper medical treatment.

3.1.9 Authority to Stop Work

ALL PERSONNEL will have the authority to temporarily stop work because of unsafe work practices, non-adherence to the Specification, or breach of containment. Written notice will be given to the Contractor stating the reason(s) for the action taken. Work will resume when the cause of the stop work action has been eliminated. The Contractor's completion clock will continue to run despite any work stoppage.

3.1.10 Agreement to Pay Fines

The Contractor agrees to pay any fines levied by any Federal, State or local agency against the Owner and the Asbestos Consultant for any violations by the Contractor or the Contractor's personnel.

3.1.11 Hold Harmless Agreement

The Abatement Contractor shall indemnify, hold harmless, and defend the Owner, Project Designer, and Consultant, partial or wholly Owner entities, and any of their agents, employees, or officers (collectively referred to as releases) from, and against, any and all losses, claims, judgments, including legal fees and expenses of any, and every, nature and description brought or recoverable against Abatement Contractor or releases by reason of any act, intentional or otherwise, or employees, arising directly, or indirectly, from the nature of the work covered by this agreement, including but not limited to, the removal and disposal of any regulated material.

3.2 Part 2 – Procedures Prior to Starting Abatement

3.2.1 Post Warning Signs and Establish Regulated Area

Warning signs will be posted at all entrances to and exits from the work area. These signs will conform to 29 CFR 1926.1101(k)(6).

3.2.2 <u>Decontamination Facilities</u>

A. Work Decontamination Facility

Decontamination facilities will be constructed in such a manner as to provide workers and/or equipment within which to decontaminate themselves upon leaving the work area. The decontamination chamber will be constructed using 6-mil polyethylene sheeting and appropriate construction materials. The decontamination facility must meet the following criteria as a minimum:

The exterior of the unit must be covered in 5/8" plywood. There will be a minimum of three chambers separated by air locks; (1) an equipment room where workers remove gross contamination and discard disposable suits; (2) a "single pass-through" shower (no shower may be used which can be passed by any person entering into or exiting from the work area); and (3) a clean (change) room where workers dress and undress. The shower must be supplied with hot and cold water as well as soap. Clean, dry towels must be available at the exit from the shower. The water from the shower must be filtered in accordance with EPA requirements or disposed of as contaminated waste. Separating each chamber and air lock will be triple curtains of polyethylene.

The decontamination unit will likely be a remote unit as this is an unoccupied area.

B. Equipment Decontamination/Waste Load-out

Equipment will be decontaminated utilizing wet methods. All waste created during the decontamination process will be disposed of as asbestos-contaminated. All materials used in the construction of a decontamination pad and the water used for decontamination must be treated as asbestos-contaminated materials.

Waste will be directly loaded into properly lined containers or staged adjacent to the designated removal area on 6-mil polyethylene sheeting. Containers will be properly wrapped in accordance with USEPA and NESHAP Disposal Requirements and will be HEPA-vacuumed, if necessary, prior to transportation.

3.2.3 Segregation of Work Areas – Gross Removal Areas

A. Isolation of Work Area

The Contractor shall isolate the entire work area for the duration of the abatement using barrier tape.

B. Protection of Existing Structure

NOT APPLICABLE

3.2.4 Preparation of Work Area for Abatement

A. Equipment

Provide all equipment necessary to accomplish the work of this contract. All equipment used will comply with all applicable OSHA provisions.

B. Water

Contractor must provide their own tank, water, and water amendments for their use. If required, the contractor shall provide their own backflow protection. Valves must be temperature and pressure rated for operation at the temperatures and pressures encountered. After completion of use, connections and fittings must be removed without damage or alteration to existing water piping and equipment. Leaking or dripping valves must be piped to the nearest drain or located over the existing sink or grade where water will not damage existing finishes or equipment.

Employ heavy-duty abrasion-resistant hoses with a pressure rating greater than the maximum pressure of the water distribution system to provide water into each work area and to each Decontamination Unit. Provide fittings as required to allow for connection to existing wall hydrants or spouts, as well as temporary water heating equipment, branch piping, showers, shut-off nozzles and equipment.

C. Electrical

Comply with applicable NEMA, NECA and UL standards and governing regulations for materials and layout of temporary electrical service.

The Contractor must provide power to the site for their own use when required. The Contractor will provide a ground fault protected power panel that will be connected to the power source

Provide identification warning signs at power outlets which are other than 110-120-volt power. Provide polarized outlets for plug-in type outlets, to prevent insertion of 110-120 volt plugs into higher voltage outlets. Dry type transformers must be used where required to provide voltages necessary for work operations.

Receptacle outlets equipped with ground fault circuit interrupters, reset button and pilot light, for plugin connection of power tools and equipment. Use only grounded extension cords: use "hard-service" cords where exposed to abrasion and traffic. Use single lengths or use waterproof connectors to connect separate lengths of electrical cords, if single lengths will not reach areas of work.

Provide general service lamps and bulbs of wattage indicated or required for adequate illumination. Protect lamps with guard cages or tempered glass enclosures, where fixtures are exposed to breakage by construction operations. Provide exterior fixtures where fixtures are exposed to the weather or moisture.

D. Sanitary Facilities

The Contractor must provide temporary sanitary facilities and shower facilities for all workers.

E. Fire Extinguishers, Portable

Comply with the applicable recommendations of NFPA Standard 10, "Standard for Portable Fire Extinguishers." Locate fire extinguishers where they are most convenient and effective for their extended purpose. As a minimum, there must be one extinguisher in each work area, one in the equipment area, and one located immediately outside the work area near the Decontamination Unit.

F. Adhesives

Where tape is used, it must be a high-quality duct tape, masking tape, or vinyl plastic tape. Where spray glue (cement) is used, it must be specifically formulated for use on polyethylene.

3.2.5 Isolation and Shutdown of Building HVAC System

NOT APPLICABLE

3.2.6 <u>Negative Pressure Establishment and Maintenance</u>

NOT APPLICABLE

3.3 Part 3 – Procedures for Friable Asbestos Abatement

3.3.1 Entry and Exit from Work Area

A. Work Area Entry

Entry into the work area must be conducted by a pre-arranged pathway. As an outdoor project likely using a remote decontamination unit, all workers must don two layers of required protective clothing, i.e. disposable whole-body suits, head covering, respirator, and shoe covers then proceed directly to the work area.

Contractor shall provide all required items for workers' protection to meet applicable OSHA and/or EPA standards.

B. Work Area Exit

All persons exiting from the work area must thoroughly decontaminate themselves to prevent the tracking out of ACM and contamination to non-contained areas. Therefore, as a minimum, the following procedure is to be followed:

- 1. Remove top layer of disposable protective clothing at the edge of the work area. Leave respirator on.
- 2. Remove bottom layer of disposable clothing in the equipment room. Leave respirator on.
- 3. Take shower, washing with soap and water.
- 4. Rinse hair with running water.

- 5. Remove respirator, wash hair.
- 6. Wash out respirator.
- 7. Exit into clean room to dry off and dress into street clothes.

It is the Contractor's responsibility to insure their personnel follow the above procedure and that ACM is not tracked outside the containment.

3.3.2 <u>Respiratory Protection during Asbestos Removal</u>

The Contractor will commence with the gross removal of asbestos in the work area in Type "C" supplied air respirators that are supplied with air of a Grade D quality or powered air purifying respirators (PAPR) in accordance with 29 CFR 1926.1101, <u>UNLESS the Contractor can provide evidence to the Asbestos Consultant that airborne fiber levels can be maintained in such a manner to permit the use of lesser respiratory protection equipment.</u> This evidence will consist of personnel air monitoring data from other projects involving the removal of similar types of materials using procedures similar to those to be used in this project. In any event, it is the responsibility of the Contractor to adequately protect his personnel in the work area and to comply with all applicable OSHA regulations.

All respiratory protection equipment to be used in the conduct of this project is to be NIOSH certified. Each worker will have a respirator personally issued and marked for his use only. The minimum type of respirator will be a half-face dual HEPA cartridge. NO RESPIRATOR OTHER THAN THIS TYPE (unless of a higher protection factor) WILL BE PERMITTED ON THE JOBSITE.

3.3.3 <u>Work Practices</u>

All work practices followed will be consistent with the OSHA standard on Occupational Exposure to Asbestos (29 CFR 1926.1101). In particular, the following work practices will be followed:

- 1. Workers shall not eat, drink, smoke, chew gum or chew tobacco in the work area, the decontamination unit, or the waste load-out area.
- 2. Workers shall always wear their respirators while inside the work. Failure to wear the appropriate respirator can result in worker removal from the jobsite

3.3.4 Asbestos Removal Procedures – General

- 1. All asbestos removal work will be performed in accordance with the requirements of the OSHA standard on Occupational Exposure to Asbestos (29 CFR 1926.1101) and OAR 340, Division 248.
- 2. All items interfering with abatement must be removed and decontaminated before being disposed of.
- 3. The Contractor will use wet methods to remove the ACM. The water used to wet the materials will be amended with a suitable wetting agent of 50% polyoxyethlene ester and 50% polyoxyethylene ether. Only airless or other low-pressure sprayers may be used to apply the amended water in a "mist." While this is a wet removal, excessive amounts of water will not be permitted to stand on the ground or within containments.
- 4. All removed ACM is to be promptly contained in 6-mil labeled polyethylene bags or wrapped in 6-mil polyethylene sheeting and then labeled. Removed ACM is not to remain onsite for excessive periods where it can dry out. Containers are not to be overfilled. As containers are filled and sealed, they are to be transported from the site as soon as possible.
- 5. All polyethylene, tape, cleaning materials, work clothing, and all other items used in the work area that cannot be completely decontaminated will be disposed of as asbestos-contaminated waste. These materials must be double-bagged in 6-mil polyethylene labeled bags and handled in the same manner as the removed ACM.

3.3.5 Asbestos Removal Procedures – Detailed

- A. Asbestos-contaminated C&D Debris Pile.
- 1. Post warning signs.
- 2. Establish a Regulated Area with barrier tape.
- 3. The Contractor is required to submit their abatement means and methods as part of the Execution Plan for approval by the Owner or Owner's Representative. The plan must specify how the regulated materials are to be removed, what containments are proposed, or if localized containment is planned (e.g. burrito wrap roll-off containers).
- 4. Prepare containers utilizing methods specified in USEPA CFR 61.145 Standard for Demolition and Renovation. Lay down 6-mil polyethylene around designated containers so that material being removed/loaded will not contact non-contaminated ground.
- 5. Immediately wrap debris containers as they are filled to completion; do not let material accumulate and remain un-covered. The containers will be properly sealed in accordance with USEPA CFR 61.145 Standard for Demolition and Renovation as they are filled and then promptly removed from the site for disposal.
- 6. Once the abatement is complete, the Contractor shall call for a visual inspection of the work area. See section 3.3.6 B for additional details.

3.3.6 <u>Clean Up Procedures</u>

A. General

All work is to be done in a professional manner and to the satisfaction of the Asbestos Consultant and Owner. All non-contaminated areas are to be protected. Cleaning supplies and equipment are to be furnished by the Contractor.

- B. Clean-up Procedure
- 1. When the gross removal of the ACM has been completed, the Contractor will then begin the process of gross clean-up. The Contractor will clean all surfaces where asbestos-contaminated soil and potential ACM residual materials remain (such as the underlying concrete slab or soil). Upon completion of gross cleaning, the Contractor will begin fine cleaning.
- 2. The Contractor will then clean all physical surfaces a second time. On completion of the fine cleaning, a visual inspection will be performed by the Asbestos Consultant or his designee. The work area must be completely free of any visible asbestos dust, debris, etc. If not, the area must be completely re-cleaned at the Contractors expense.
- C. Equipment Decontamination

Equipment, machinery, tools, etc., used within the work area will not be removed without first being thoroughly cleaned with amended water. An equipment decontamination pad may be necessary to fully clean any heavy equipment (i.e. lifts, loaders, etc.) that might be used during abatement. Materials used to construct a decontamination pad and water used to decontaminate equipment must be treated as asbestos-contaminated materials.

3.3.7 <u>Air Monitoring</u>

A. General

Asbestos air monitoring will be completed along the perimeter of the work area to ensure that proper dust suppression techniques are used. Analysis of asbestos air samples will be completed by PCM by a qualified laboratory or properly trained and certified personnel. Asbestos air sampling will be conducted while all abatement work is occurring. Final clearance asbestos air samples will be collected following final visual clearance by an asbestos inspector and approval by Owner, Owner's Representative, or the Asbestos Consultant. The air samples will be collected by a qualified asbestos air sampling technician. Analysis of air samples will be completed by a certified laboratory and/or a qualified and accredited PCM analyst.

Asbestos air monitoring reports will be provided to the Owner within 48-hours of collection with the daily report.

B. Airborne Fiber Levels

If an air sample concentration exceeds the average background fiber count as determined by the Asbestos Consultant or 0.01 f/cc, whichever is greater, then the Asbestos Consultant or his designee may stop work and require additional engineering controls used to suppress dust. The Contractor will be responsible for any additional controls required to maintain airborne fiber levels below the identified limit. TEM may be used to re-analyze an exceeded sample if the PCM analyst believes the fiber count to be elevated due to potential non-asbestos fibers.

3.3.8 Disposal of Asbestos Waste

- A. General
- 1. All asbestos and asbestos-contaminated waste must be sealed in approved containers in accordance with USEPA CFR 61.145 Standard for Demolition and Renovation. The containers are to be labeled, transported and disposed of in accordance with the applicable OSHA and EPA Regulations. At the conclusion of the job, all polyethylene material will be disposed of as asbestos-contaminated waste material.
- 2. Only an approved and licensed asbestos waste hauler will be permitted to remove the material from the jobsite and transport it to the landfill. The Contractor will be responsible for transportation of the material to the landfill, and the submission of receipts from the landfill to the Asbestos Consultant as evidence that the material was disposed of in an approved manner. The Owner must receive the final landfill tickets.
- B. Waste Disposal Site
- 1. The Owner will be responsible for obtaining prior approval for a disposal site for the asbestos waste in compliance with the latest ODEQ and USEPA regulations.
- 2. The Owner shall strictly adhere to all precautions necessary for the safety and health of the workmen in accordance with the latest version of the applicable OSHA and USEPA Regulations, especially 29 CFR 1926.1101.
- C. Transportation

All asbestos materials must be carried directly to the previously approved asbestos landfill. The Contractor will contact the landfill to make arrangements regarding the time of the dump operation.

D. Alternate Methods

Alternate handling and packaging systems for the debris that maintain the integrity of the disposal systems will be considered by the Asbestos Consultant.

E. Burning

Burning of materials from the abated area will not be permitted.

F. General Debris

All trash and debris are to be removed from the property by the Contractor daily.

G. Wastewater

Wastewater may be disposed of by filtering the asbestos-contaminated water in accordance with USEPA regulations, then disposing of the filtered water in a sanitary sewer system. Wastewater that is not filtered cannot be placed into the public sewer system or disposed of in a location other than an approved disposal site.

All wastewater from the shower and/or any sinks must be disposed of in a manner similar to that of solid waste materials previously specified in this Section.

4 References

- AHERA regulations: <u>https://www.epa.gov/asbestos/asbestos-and-school-buildings</u>
- NESHAP regulations: <u>https://www.epa.gov/asbestos/overview-asbestos-national-emission-</u> <u>standards-hazardous-air-pollutants-neshap</u>
- OSHA asbestos regulations: <u>https://www.osha.gov/SLTC/asbestos/</u>
- DOL website: <u>https://www.dol.gov/whd/regs/compliance/whdfs66.pdf</u>.
- OAR 340, Division 248 Asbestos Requirements

Bid Form







BID FORM							
FORMER MARKWARDT BROTHERS SITE							
112 W CHOCKTOOT STREET, CHILOQUIN, OREGON 97624							
BUILDING DEBRIS PILE REMOVAL - SCOPE OF WORK							
Company:							
Address:							
Authorized Representative:							
Signature:							
Cell Number:							
Email:							
LUMP SUM PRICES	-						
	Quantity	Units	Cost (\$)	Notes			
1.) Project Submittals - Execution Plan, HASP, Traffic Plan	1	LS	\$				
2.) Project Management, Permits, Notifications, Completion Report	1	LS	\$				
3.) Project Mobilization and Demobilization	1	LS	\$				
4.) ACM-Contaminated Pile Removal & Disposal (up to 450 CY)	1	LS	\$				
5.) Site Restoration	1	LS	\$				
LUMP SUM	I SUBTO	DTAL	\$				
REMOVAL AND DISPOSAL DETAILS							
10050700		ļ					
ASBESTOS	450						
ACM-Contaminated Building Debris Pile	450	CY					
SITE RESTORATION							
Grade Area to Match Slab, Clean Slab, Fill Depressions with #57 Stone or	<1	Acre					
Equivalent (up to 2 CY of Fill Material)		Acie					
TIME AND MATERIAL COSTS							
Additional ACM-Contaminated Building Debris Removal and Disposal	1	CY					
Additional #57 Stone or Equivalent Fill Material	1	CY					
SCHEDULE:							
1.) Project Submittals - Execution Plan, HASP, Traffic Plan		working	n davs				
2.) Project Management, Permits, Notifications, Completion Report		working					
3.) Project Mobilization and Demobilization		working	, ,				
4.) ACM-Contaminated Pile Removal & Disposal		working					
5.) Site Restoration		working					
Total Project Duration			ig days				
		WORKIN					
PROJECT ASSUMPTIONS							
Contractor is responsible for all removal, packaging, manifesting, transportat	ion, and dis	posal of	all ACM-contaminated ma	aterials and any other waste			
referenced in the Scope of Work. All permits, certifications, fees, notifications etc. required to complete the Sco	ope of Work	are to h	e prepared and baid by C	Contractor.			
All submittals will be reviewed by the Owner and/or Owner's consultant for a	-						
	•		•				
Contractor is responsible for the completion of referenced tasks. No additional fees will be paid for re-cleaning insufficient work.							
Contractor is responsible for personnel air monitoring as required by Federal, State and local regulations. Contractor is responsible for all equipment, materials, and PPE as necessary for the performance of the work.							
Contractor is responsible for all equipment, materials, and PPE as necessary for the performance of the work. Contractor is responsible for preparing a health and safety plan that incorporates all regulatory requirements as well as requirements of the primary							
contractor, when applicable.	ales all regu	natory fe	equirements as well as let	quirements of the plittid y			
Contractor is responsible for providing all safety equipment required to perform the specified work.							
Contractor is responsible for all temporary utilities (water, electricity, personnel facilities, etc.) and associated fees required to perform the specified work.							
It is assumed that the scope of work will be completed during one mobilization and the contractor will have unimpeded access to the work areas. Coordination may be required with the City/Town for potential full or partial road closure.							
By virtue of the authorized signature on this bid form, the bidder affirms that documents and all attachments.		will com	ply with all conditions sta	ted in the project design			

Tables





TABLE 1: SUMMARY OF BULK SAMPLE ANALYSISFACILITY NAME: FORMER MARKWARDT BROTHERS GARAGE
CHILOQUIN, KLAMATH COUNTY, OREGON

HA ID	Date	HA Description	Material Location	Percent and Type of Asbestos Detected ¹	Estimated Quantity	Type of ACM ²	Friability ³	Physical Condition
RP-01-01	8/18/21	Shingles	Rubble pile (east)	NAD	N/A	N/A	NF	Poor
RP-01-02	8/18/21	Shingles	Rubble pile (north)	NAD	N/A	N/A	NF	Poor
RP-02-01a	8/18/21	Drywall (White texture w/ paint)	Rubble pile (west)	2% CH	450 CY	Misc. Cat 1	F	Poor
RP-02-01b	8/18/21	Drywall (Cream tape)	Rubble pile (west)	NAD	N/A	N/A	F	Poor
RP-02-01c	8/18/21	Drywall (White joint compound)	Rubble pile (west)	2% CH	450 CY	Misc. Cat 1	F	Poor
RP-02-01d	8/18/21	Drywall (White drywall w/ brown paper)	Rubble pile (west)	NAD	N/A	N/A	F	Poor
RP-02-02a	8/18/21	Drywall (Cream tape)	Rubble pile (north)	NAD	N/A	N/A	NF	Poor
RP-02-02b	8/18/21	Drywall (White joint compound)	Rubble pile (north)	2% CH	450 CY	Misc. Cat 1	F	Poor
RP-02-02c	8/18/21	Drywall (White drywall w/ brown paper)	Rubble pile (north)	NAD	N/A	N/A	NF	Poor
RP-03-01	8/18/21	Gray caulk	Rubble pile (west)	NAD	N/A	N/A	NF	Poor
RP-03-02	8/18/21	Gray caulk	Rubble pile (east)	NAD	N/A	N/A	NF	Poor

Notes:

(1) CH = Chrysotile; AM = Amosite; CR = Crocidolite; AN = Anthophyllite; AC = Actinolite; NAD = No Asbestos Detected

(2) Misc = Miscellaneous; TSI = Thermal System Insulation; SM= Surfacing Material

(3) F = Friable; NF - Non friable. For ACMs only: I = Non-Friable Category I; II = Non-Friable Category II

NM - not measured

LF = linear feet PACM = Presumed Asbestos-Containing Materials

n/a - not applicable

SF = square feet CY = Cubic Yards

TABLE 2: SUMMARY OF TCLP LEAD SAMPLESFACILITY NAME: FORMER MARKWARDT BROTHERS GARAGECHILOQUIN, KLAMATH COUNTY, OREGON

Sample ID	Date	e Location Result		Estimated Quantity	Physical Condition
RP-01	8/18/21	Rubble pile (east)	BRL	N/A	Deteriorated
RP-02	8/18/21	Rubble pile (west)	BRL	N/A	Deteriorated

Notes:


NM - not measured


n/a - not applicable BRL = Below Laboratory Reporting Limit

Figures









Appendix A Photographic Log





PHOTOGRAPHIC LOG Site Location: Former Markwardt Brothers Garage, Chiloquin, Oregon Facility #: TBD Photo No. Date: 1/28/2022 Direction Photo Taken: West West Description: Debris Pile Debris Pile

Photo No. 2	Date: 1/28/2022	
Direction Phote		
South		The second secon
Description:		
Debris Pile		

PHOTOGRAPHIC LOG Site Location: Former Markwardt Brothers Garage, Chiloquin, Oregon Facility #: TBD Photo No. Date: 1/28/2022 Direction Photo Taken: South Description: Debris Pile

Photo No. 4	Date: 1/28/2022	
4 Direction Photo		
East		
Description:		
Debris Pile – Deta Materials	iled View of	



PHOTOGRAPHIC LOG				Cardno Shaping the Future
Client Name: C	Client Name: City of Chiloquin, OR		Site Location: Former Markwardt Brothers Garage, Chiloquin, Oregon	Facility #: TBD
Photo No. 5	Date: 4/1/2021			·
Direction Photo	Taken:		114	<u>atin</u>
East				
Description: Debris Pile with ur concrete slab and				

Photo No. 6	Date: 4/1/2021
Direction Photo	Taken:
South	
Description:	
Description.	
Debris Pile – Easte debris pile	ern side of the



Appendix B Laboratory Analytical Reports







Report for:

W. Ashton Smithwick Cardno 6611 Bay Circle Suite 220 Norcross, GA 30071

Regarding: Project: CH860Q100 EML ID: 2718074

Approved by:

Approved Signatory Balu Krishnan Dates of Analysis: Asbestos PLM: 08-27-2021

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267) NVLAP Lab Code 200738-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins EMLab P&K ("the Company") shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

6301 NW 5th way, Suite#: 1410, Ft. Lauderdale, FL 33309 (866) 871-1984 Fax (954) 776-8485 www.emlab.com

Client: Cardno C/O: W. Ashton Smithwick Re: CH860Q100

ASBESTOS PLM REPORT

Total Samples Submitted:	6	
Total Samples Analyzed:	6	
Total Samples with Layer Asbestos Content > 1%:	2	
		ĩ

Date of Receipt: 08-25-2021

Date of Report: 08-27-2021

Location: RP-01-01, Shingles

Sample Layers	Asbestos Content
Black Roofing Shingle with Gray pebbles	ND
Composite Non-Asbestos Content:	15% Glass Fibers
Sample Composite Homogeneity:	Good

Location: RP-01-02, Shingles

Sample Layers	Asbestos Content
Black Roofing Shingle with Gray pebbles	ND
Composite Non-Asbestos Content:	15% Glass Fibers
Sample Composite Homogeneity:	Good

Location: RP-02-01, Drywall

Location. KI -02-01, Diywan		
Sample Layers	Asbestos Content	
White Texture with Paint	2% Chrysotile	
Cream Tape	ND	
White Joint Compound	2% Chrysotile	
White Drywall with Brown Paper	ND	
Composite Asbestos Fibrous Content:	<1% Asbestos	
Composite Non-Asbestos Content:	15% Cellulose	
Sample Composite Homogeneity:	Moderate	

Comments: Composite asbestos content provided is only for Drywall/Joint compound. Composite content provided for this analysis has been performed by following the NESHAP guidelines.

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. Eurofins EMLab P&K reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

A "Version" indicated by -"x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

I ab ID-Version*: 13001099-1

Lab ID-Version 13001098-1

Lab ID-Version 13001097-1

Lab ID-Version #: 13001100-1

6301 NW 5th way, Suite#: 1410, Ft. Lauderdale, FL 33309 (866) 871-1984 Fax (954) 776-8485 www.emlab.com

Client: Cardno C/O: W. Ashton Smithwick Re: CH860Q100

Date of Receipt: 08-25-2021 Date of Report: 08-27-2021

ASBESTOS PLM REPORT

Location: RP-02-02, Drywall

Sample Layers	Asbestos Content
Cream Tape	ND
White Joint Compound	2% Chrysotile
White Drywall with Brown Paper	ND
Composite Asbestos Fibrous Content:	< 1% Asbestos
Composite Non-Asbestos Content:	15% Cellulose
Sample Composite Homogeneity:	Moderate

Comments: Composite asbestos content provided is only for Drywall/Joint compound. Composite content provided for this analysis has been performed by following the NESHAP guidelines.

Location: RP-03-01, Gray Caulk

Sample Layers	Asbestos Content
Gray Caulk with Paint	ND
Sample Composite Homogeneity:	Good

Location: RP-03-02, Gray Caulk

Sample Layers	Asbestos Content
Gray Caulk with Paint	ND
Sample Composite Homogeneity:	Good

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. Eurofins EMLab P&K reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

A "Version" indicated by -"x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Eurofins EPK Built Environment Testing, LLC

EMLab ID: 2718074, Page 3 of 3

Lab ID-Version : 13001102-1

Lab ID-Version #: 13001101-1



Pace Analytical® ANALYTICAL REPORT

August 27, 2021

Cardno - Peachtree Corners, GA

Sample Delivery Group: Samples Received: Project Number: Description:

L1393214 08/20/2021 CHIL0Q120 Chiloquin, OR

Report To:

William Smithwick 6611 Bay Circle Suite 220 Peachtree Corners, GA 30071 Тс Ss Cn Su GI Al Sc

Entire Report Reviewed By:

Vubb law

Jeff Carr Project Manager

Results relate only to the items tested or calibrated and are reported as rounded values. This test report shall not be reproduced, except in full, without written approval of the laboratory. Where applicable, sampling conducted by Pace Analytical National is performed per guidance provided in laboratory standard operating procedures ENV-SOP-MTJL-0067 and ENV-SOP-MTJL-0068. Where sampling conducted by the customer, results relate to the accuracy of the information provided, and as the samples are received.

Pace Analytical National

12065 Lebanon Rd Mount Juliet, TN 37122 615-758-5858 800-767-5859 www.pacenational.com

ACCOUNT: Cardno - Peachtree Corners, GA

PROJECT: CHIL0Q120

SDG: L1393214

DATE/TIME: 08/27/2114:32

PAGE: 1 of 35

TABLE OF CONTENTS

Cp: Cover Page		1
Tc: Table of Contents		2
Ss: Sample Summary		4
Cn: Case Narrative		5
Su: Summary Results		6
6010D Metals (ICP)		7
Sample Result Inorganic Analysis Data Sheet		7
L1393214-01 08/27/21 02:03 ICP12		7
L1393214-02 08/27/21 02:06 ICP12		8
BLANK(R3697192-1) WG1729585 08/27/21 01:2	24 ICP12	9
LCS(R3697192-2) WG1729585 08/27/21 01:26	ICP12	10
MS(R3697192-4) WG1729585 08/27/21 01:34 I	CP12	11
MSD(R3697192-5) WG1729585 08/27/21 01:36	ICP12	12
SD(R3697192-3) WG1729585 08/27/21 01:32 K	CP12	13
Calibration Verification		14
ICP12 082621ICP12		14
Blank		17
ICP12 082621ICP12		17
ICP Interference Check Sample		19
ICP12 08/26/21 16:42		19
ICP12 08/26/21 23:24		20
ICP12 08/27/21 05:04		21
Matrix Spike / Duplicate		22
WG1729585 MS(R3697192-4) MSD(R3697192-	5)	22
Laboratory Control Sample / Duplicate		23
WG1729585 LCS(R3697192-2)		23
Serial Dilution		24
WG1729585 SD(R3697192-3)		24
Detection Limit Summary		25
6010D - Waste		25
Interelement Correction Factor		26
ICP12 08/24/21 13:38		26
Linear Dynamic Range		28
ICP12 06/16/21 08:38		28
Analysis Log		29
ICP12 082621ICP12 08/26/21 16:03		29
Initial Calibration Recovery		30
ICP12 082621ICP12 08/26/21 16:03		30
Initial Calibration		32
ICP12 082621ICP12 08/26/21 16:03		32
ACCOUNT: PROJECT:	SDG:	DATE/TIME:


¹ Cp ² Tc ³ Ss ⁴ Cn ⁵ Su ⁶ GI ⁷ AI ⁸ Sc

PROJECT: CHILOQ120

L1393214

PAGE: 2 of 35

GI: Glossary of Terms	33
Al: Accreditations & Locations	34
Sc: Sample Chain of Custody	35



PROJECT: CHILOQ120 SDG: L1393214 DATE/TIME: 08/27/2114:32

PAGE: 3 of 35

SAMPLE SUMMARY

		Collected by	Collected date/time	Received da	te/time
		A. Smithwick	08/18/21 00:00	08/20/21 09:	:00
Batch	Dilution	Preparation	Analysis	Analyst	Location
		date/time	date/time		
WG1728099	1	08/24/21 15:04	08/24/21 15:04	TDW	Mt. Juliet, TN
WG1729585	1	08/25/21 18:19	08/27/21 02:03	CCE	Mt. Juliet, TN
		Collected by	Collected date/time	Received da	te/time
		A. Smithwick	08/18/21 00:00	08/20/21 09:	:00
Batch	Dilution	Preparation	Analysis	Analyst	Location
		date/time	date/time		
WG1728099	1	08/24/21 15:04	08/24/21 15:04	TDW	Mt. Juliet, TN
	WG1728099 WG1729585 Batch	WG1728099 1 WG1729585 1 Batch Dilution	A. Smithwick Batch Dilution WG1728099 1 WG1729585 1 08/24/21 15:04 WG1729585 1 08/25/21 18:19 Collected by A. Smithwick Batch Dilution Preparation date/time	A. Smithwick08/18/21 00:00BatchDilutionPreparation date/timeAnalysis date/timeWG1728099108/24/21 15:04 08/25/21 18:1908/24/21 15:04 08/27/21 02:03WG1729585108/25/21 18:19 Collected by A. SmithwickCollected date/time 08/18/21 00:00BatchDilutionPreparation date/timeAnalysis date/time	A. Smithwick08/18/21 00:0008/20/21 09BatchDilutionPreparation date/timeAnalysis date/timeAnalysis date/timeWG1728099108/24/21 15:0408/24/21 15:04TDW O8/27/21 02:03WG1729585108/25/21 18:1908/27/21 02:03CCECollected by A. SmithwickCollected date/time 08/18/21 00:00Received da 08/20/21 09BatchDilutionPreparation date/timeAnalysis date/timeAnalysis date/time

Ср

²Tc

Ss

SDG: L1393214 DATE/TIME: 08/27/2114:32

CASE NARRATIVE

All sample aliquots were received at the correct temperature, in the proper containers, with the appropriate preservatives, and within method specified holding times, unless qualified or notated within the report. Where applicable, all MDL (LOD) and RDL (LOQ) values reported for environmental samples have been corrected for the dilution factor used in the analysis. All Method and Batch Quality Control are within established criteria except where addressed in this case narrative, a non-conformance form or properly qualified within the sample results. By my digital signature below, I affirm to the best of my knowledge, all problems/anomalies observed by the laboratory as having the potential to affect the quality of the data have been identified by the laboratory, and no information or data have been knowingly withheld that would affect the quality of the data.

ubb land

Jeff Carr Project Manager



SDG: L1393214

PAGE: 5 of 35 6010D Metals (ICP)

SDG: L1393214 DATE/TIME: 08/27/21 14:22

Lab Sample ID:	L1393214-01	SDG:	L1393214
Client Sample ID:	RP-01	Collected Date/Time:	08/18/21 00:00
Lab File ID:	20210827020335	Received Date/Time:	08/20/21 09:00
Instrument ID:	ICP12	Preparation Date/Time:	08/25/21 18:19
Analytical Batch:	WG1729585	Analysis Date/Time:	08/27/21 02:03
Dilution Factor:	1	Prep Method:	3015
Analytical Method:	6010D	Sample Vol Used:	
Matrix:	Waste	Initial Wt/Vol:	5 mL
Total Solids (%):		Final Wt/Vol:	50 mL

Analyte	CAS	Result	Qualifier	MDL	RDL
		mg/l		mg/l	mg/l
Lead	7439-92-1	ND		0.0330	0.100

SDG: L1393214

ab Sample ID:	L1393214-02	SDG:	L1393214
Client Sample ID:	RP-02	Collected Date/Time:	08/18/21 00:00
ab File ID:	20210827020616	Received Date/Time:	08/20/21 09:00
nstrument ID:	ICP12	Preparation Date/Time:	08/25/21 18:19
Analytical Batch:	WG1729585	Analysis Date/Time:	08/27/21 02:06
Dilution Factor:	1	Prep Method:	3015
nalytical Method:	6010D	Sample Vol Used:	
Aatrix:	Waste	Initial Wt/Vol:	5 mL
Total Solids (%):		Final Wt/Vol:	50 mL

Analyte	CAS	Result	Qualifier	MDL	RDL
		mg/l		mg/l	mg/l
Lead	7439-92-1	ND		0.0330	0.100

Total Solids (%):		Final Wt/Vol:	50 mL
Matrix:	Waste	Initial Wt/Vol:	5 mL
Analytical Method:	6010D	Sample Vol Used:	
Dilution Factor:	1	Prep Method:	3015
Analytical Batch:	WG1729585	Analysis Date/Time:	08/27/21 01:24
nstrument ID:	ICP12	Preparation Date/Time:	08/25/21 18:19
Lab File ID:	20210827012400	Received Date/Time:	
Client Sample ID:	BLANK	Collected Date/Time:	
Lab Sample ID:	R3697192-1	SDG:	L1393214

Analyte	CAS	Result	Qualifier	MDL	RDL
		mg/l		mg/l	mg/l
Lead	7439-92-1	U		0.0333	0.100

ACCOUNT:

Cardno - Peachtree Corners, GA

DATE/TIME: 08/27/2114:22

SAMPLE NO.: R3697192-2

Lab Sample ID: Client Sample ID:	R3697192-2 LCS	SDG: Collected Date/Time:	L1393214
Lab File ID:	20210827012625	Received Date/Time:	
Instrument ID:	ICP12	Preparation Date/Time:	08/25/21 18:19
Analytical Batch:	WG1729585	Analysis Date/Time:	08/27/21 01:26
Dilution Factor:	1	Prep Method:	3015
Analytical Method:	6010D	Sample Vol Used:	
Matrix:	Waste	Initial Wt/Vol:	5 mL
Total Solids (%):		Final Wt/Vol:	50 mL

Analyte	CAS	Result	Qualifier	MDL	RDL
		mg/l		mg/l	mg/l
Lead	7439-92-1	9.77		0.0333	0.100

SAMPLE NO.: R3697192-4

Lab Sample ID:	R3697192-4	SDG:	L1393214
Client Sample ID:	MS	Collected Date/Time:	08/16/21 11:15
Lab File ID:	20210827013429	Received Date/Time:	08/20/21 08:00
nstrument ID:	ICP12	Preparation Date/Time:	08/25/21 18:19
Analytical Batch:	WG1729585	Analysis Date/Time:	08/27/21 01:34
Dilution Factor:	1	Prep Method:	3015
nalytical Method:	6010D	Sample Vol Used:	
Aatrix:	Waste	Initial Wt/Vol:	5 mL
Total Solids (%):		Final Wt/Vol:	50 mL

Analyte	CAS	Result	Qualifier	MDL	RDL
		mg/l		mg/l	mg/l
Lead	7439-92-1	9.83		0.0333	0.100

1-IN

SDG: L1393214

ab Sample ID:	R3697192-5	SDG:	L1393214
Client Sample ID:	MSD	Collected Date/Time:	08/16/21 11:15
ab File ID:	20210827013654	Received Date/Time:	08/20/21 08:00
nstrument ID:	ICP12	Preparation Date/Time:	08/25/21 18:19
Analytical Batch:	WG1729585	Analysis Date/Time:	08/27/21 01:36
Dilution Factor:	1	Prep Method:	3015
nalytical Method:	6010D	Sample Vol Used:	
Matrix:	Waste	Initial Wt/Vol:	5 mL
Total Solids (%):		Final Wt/Vol:	50 mL

Analyte	CAS	Result	Qualifier	MDL	RDL
		mg/l		mg/l	mg/l
Lead	7439-92-1	9.86		0.0333	0.100

SAMPLE NO.: R3697192-3

ab Sample ID:	R3697192-3	SDG:	L1393214
Client Sample ID:	SD	Collected Date/Time:	08/16/21 11:15
ab File ID:	20210827013201	Received Date/Time:	08/20/21 08:00
nstrument ID:	ICP12	Preparation Date/Time:	08/25/21 18:19
Analytical Batch:	WG1729585	Analysis Date/Time:	08/27/21 01:32
Dilution Factor:	5	Prep Method:	3015
Analytical Method:	6010D	Sample Vol Used:	
Aatrix:	Waste	Initial Wt/Vol:	5 mL
Total Solids (%):		Final Wt/Vol:	50 mL

Analyte	CAS	Result	Qualifier	MDL	RDL
		mg/l		mg/l	mg/l
Lead	7439-92-1	ND		0.167	0.500

CALIBRATION VERIFICATION

SDG:	L1393214	Calibration (begin) date/time:	08/26/21 16:03
Instrument ID:	ICP12	Calibration (end) date/time:	08/26/21 16:20
Analytical Method:	6010D	Analytical Run:	082621ICP12
Concentration Units:	mg/l		

			IC	v			ICVI	LL			cc	v	
	Sample ID:	1	ICP120826	6211623-	-2		ICP120826	211633	-2		ICP12082	7210111-	2
Analyte		True	Found	%R	%RSD	True	Found	%R	%RSD	True	Found	%R	%RSD
LEAD		1	0.9993387	99.9 0	0.206000	0.0050	0.005616919	112	20.300000	0.50	0.5050739	101	0.361000

ICV Limits: 90 - 110	ICVLL Limits: 80 - 120	CCV Limits: 90 - 110	CCVLL Limits: 50 - 150	
ACCOUNT:	PROJECT:	SDG:	DATE/TIME:	PAGE:
Cardno - Peachtree Corners, GA	CHILOQ120	L1393214	08/27/2114:22	14 of 35

CALIBRATION VERIFICATION

SDG:	L1393214	Calibration (begin) date/time:	08/26/21 16:03
Instrument ID:	ICP12	Calibration (end) date/time:	08/26/21 16:20
Analytical Method:	6010D	Analytical Run:	082621ICP12
Concentration Units:	mg/l		

			cc	V			C	cv			cc	:V	
	Sample ID:		ICP120827	7210118	-2		ICP12082	7210150	-2		ICP12082	2721021	1
Analyte		True	Found	%R	%RSD	True	Found	%R	%RSD	True	Found	%R	%RSD
LEAD		0.50	0.5042665	101	0.314000	0.50	0.50595	101	0.671000	0.50	0.5113141	102	0.572000

ICV Limits: 90 - 110	ICVLL Limits: 80 - 120	CCV Limits: 90 - 110	CCVLL Limits: 50 - 150	
ACCOUNT:	PROJECT:	SDG:	DATE/TIME:	PAGE:
Cardno - Peachtree Corners, GA	CHIL0Q120	L1393214	08/27/21 14:22	15 of 35

CALIBRATION VERIFICATION

SDG:	L1393214	Calibration (begin) date/time:	08/26/21 16:03	
Instrument ID:	ICP12	Calibration (end) date/time:	08/26/21 16:20	
Analytical Method:	6010D	Analytical Run:	082621ICP12	
Concentration Units:	mg/l			

	CCVLL						
	Sample ID:		ICP1208272	10852-:	2		
Analyte		True	Found	%R	%RSD		
LEAD		0.0050	0.003182933	63.7 0	31.600000		

ICV Limits: 90 - 110	ICVLL Limits: 80 - 120	CCV Limits: 90 - 110	CCVLL Limits: 50 - 150	
ACCOUNT:	PROJECT:	SDG:	DATE/TIME:	PAGE:
Cardno - Peachtree Corners, GA	CHIL0Q120	L1393214	08/27/2114:22	16 of 35

SDG: Instrument Analytical N		L1393214 ICP12 6010D		Cal	ibration (beg ibration (end alytical Run:	in) date/time:) date/time:	08/26	5/21 16:03 5/21 16:20 21ICP12	
 Analytical N	Sample ID:		ICB Qual	CCB Result	CCB Qual	CCB Result	CCB Qual		BLANK Qual
Analyte	File ID:	20210826162546 mg/l	5-2	20210827011358 mg/l	-2	20210827012110- mg/l	2	20210827012400 mg/l	
LEAD		0.001593365	U	0.0009517472	U	0.0009832964	U	U	

BLANKS

3-IN

SDG: L1393214 DATE/TIME: 08/27/2114:22

PAGE: 17 of 35

3-IN			BLANKS					
SDG:	L1393214		Calibra	tion (begin) date/1	time:	08/26/21 16:03	3	
Instrument ID: ICP12			Calibra	08/26/21 16:20				
Analytical Method:	6010D	Analytical Run:			082621ICP12			
	•	CCB Result 20210827015256	CCB Qual 6-2	CCB Result 20210827021417	CCB Qual			
	Analyte	mg/l		mg/l				
	LEAD	0.0004943883	U	-0.0005048188	U			

SDG: L1393214 DATE/TIME: 08/27/2114:22

PAGE: 18 of 35

INTERFERENCE CHECK SAMPLE

SDG: Instrument ID: Instrument Run:	L1393214Analytical MethICP12Date:082621ICP12			ethod: 6010D 08/26/2116:42				
Analyte	True	Found	ł	True	Foun	d		
	ICSA	ICSA	ICSA	ICSAB	ICSAB	ICSAB		
	mg/l	mg/l	% Rec.	mg/l	mg/l	% Rec.		
ALUMINUM	500	502.0379	100	500	501.9921	100		
ANTIMONY	0	0.02755975		0.50	0.5643993	113		
ARSENIC	0	-0.03494365		0.50	0.512478	102		
BARIUM	0	0.002959076		0.50	0.5423834	108		
BERYLLIUM	0	-0.00007358297		0.50	0.4979079	99.60		
BORON	0	-0.09021902		1	0.9626316	96.30		
CADMIUM	0	0.0009786234		1	1.087652	109		
CALCIUM	500	508.4613	102	500	507.7226	102		
CERIUM	0	0.1681203		0	0.1955043			
CHROMIUM	0	0.0009804087		0.50	0.5208367	104		
COBALT	0	-0.0004623029		0.50	0.5075576	102		
COPPER	0	0.005100224		0.50	0.5784515	116		
HOT WATER SOL. BORON	0	-0.09021902		0	0.9626316			
RON	200	201.8789	101	200	203.5889	102		
LANTHANUM	0	-0.005494578		0	-0.009495438			
LEAD	0	-0.03503772		1	0.9580334	95.80		
LITHIUM	0	0.001406181		0	0.003878799			
MAGNESIUM	500	514.5004	103	500	517.2876	103		
MANGANESE	0	0.004084937		0.50	0.5137185	103		
MOLYBDENUM	0	0.000217832		0.50	0.5360155	107		
NICKEL	0	-0.003223017		1	0.9933387	99.30		
PHOSPHORUS	0	0.005994708		0	0.005210479			
POTASSIUM	0	-0.09904029		0	-0.04067108			
SELENIUM	0	0.02472459		0.50	0.5785699	116		
SILICON	0	-0.01150722		1	1.071702	107		
SILVER	0	-0.0007341132		1	1.114799	111		
SODIUM	0	0.1562164		0	0.1747456			
STRONTIUM	0	0.003898679		0	0.004028935			
SULFUR	0	-0.07472075		0	-0.09834596			
THALLIUM	0	-0.01106474		0.50	0.4809626	96.20		
TIN	0	-0.01255101		0.50	0.477174	95.40		
TITANIUM	0	0.009308359		0.50	0.5261634	105		
VANADIUM	0	-0.0007290835		0.50	0.5038603	101		
ZINC	0	0.0002950366		1	0.9970569	99.70		

ICSA Limits: 80 - 120

ICSAB Limits: 80 - 120

ACCOUNT: Cardno - Peachtree Corners, GA PROJECT: CHIL0Q120 SDG: L1393214 DATE/TIME: 08/27/2114:22

PAGE: 19 of 35

INTERFERENCE CHECK SAMPLE

Analyte	True ICSA mg/l	Found ICSA	4	-	6010D 08/26/21 23:24		
ALUMINUM		/CSA		True	Found		
ALUMINUM	mg/l		ICSA	ICSAB	ICSAB	ICSAB	
ALUMINUM		mg/l	% Rec.	mg/l	mg/l	% Rec.	
	500	551.2503	110	500	575.7381	115	
ANTIMONY	0	0.03180174		0.50	0.5606752	112	
ARSENIC	0	-0.01864892		0.50	0.5438317	109	
BARIUM	0	0.003478609		0.50	0.5586314	112	
BERYLLIUM	0	-0.00004508121		0.50	0.5439089	109	
BORON	0	-0.1022247		1	1.068909	107	
CADMIUM	0	0.00076298		1	1.126211	113	
CALCIUM	500	535.6206	107	500	544.739	109	
CERIUM	0	0.2528661		0	0.3506344		
CHROMIUM	0	0.0008172511		0.50	0.5295011	106	
COBALT	0	-0.0003726358		0.50	0.5287809	106	
COPPER	0	0.005507577		0.50	0.5803618	116	
HOT WATER SOL. BORON	0	-0.1022247		0	1.068909		
RON	200	218.5789	109	200	221.237	111	
ANTHANUM	0	-0.005088498		0	-0.007204261		
EAD	0	-0.03669559		1	0.9730582	97.30	
ITHIUM	0	0.001343081		0	0.001781075		
MAGNESIUM	500	570.2284	114	500	578.9104	116	
MANGANESE	0	0.004378487		0.50	0.5503041	110	
MOLYBDENUM	0	0.001395187		0.50	0.5510551	110	
NICKEL	0	-0.003192652		1	1.022575	102	
PHOSPHORUS	0	0.01065495		0	0.01082105		
POTASSIUM	0	0.01223173		0	0.03494858		
SELENIUM	0	0.03445835		0.50	0.5990063	120	
SILICON	0	0.0003109475		1	1.094995	109	
SILVER	0	-0.0008659254		1	1.145005	115	
SODIUM	0	0.2397492		0	0.262562		
STRONTIUM	0	0.004272831		0	0.004531666		
SULFUR	0	-0.0847923		0	-0.08784118		
THALLIUM	0	-0.01751272		0.50	0.495921	99.20	
TIN	0	-0.01262536		0.50	0.4756486	95.10	
TITANIUM	0	0.01215882		0.50	0.5784899	116	
VANADIUM	0	-0.002840961		0.50	0.5473146	109	
ZINC	0	0.0001905174		1	1.094725	109	

ICSAB Limits: 80 - 120

ACCOUNT: Cardno - Peachtree Corners, GA PROJECT: CHIL0Q120 SDG: L1393214 DATE/TIME: 08/27/21 14:22

PAGE: 20 of 35

INTERFERENCE CHECK SAMPLE

SDG: Instrument ID: Instrument Run:	L1393214 ICP12 082621ICP12	Ana Dat	6010D 08/27/21 05:04				
Analyte	True	Found	ł	True	Foun	d	
	ICSA	ICSA	ICSA	ICSAB	ICSAB	ICSAB	
	mg/l	mg/l	% Rec.	mg/l	mg/l	% Rec.	
ALUMINUM	500	502.5224	101	500	503.1821	101	
ANTIMONY	0	0.01808757		0.50	0.5479234	110	
ARSENIC	0	-0.01754558		0.50	0.4844012	96.90	
BARIUM	0	0.002872428		0.50	0.5287579	106	
BERYLLIUM	0	-0.00006848697		0.50	0.4789366	95.80	
BORON	0	-0.07727791		1	0.9152908	91.50	
CADMIUM	0	0.001028797		1	1.050905	105	
CALCIUM	500	458.3567	91.70	500	457.1739	91.40	
CERIUM	0	0.05331246		0	0.08013209		
CHROMIUM	0	0.001037285		0.50	0.4979886	99.60	
COBALT	0	-0.0001226026		0.50	0.4784037	95.70	
COPPER	0	0.003390379		0.50	0.5581955	112	
HOT WATER SOL. BORON	0	-0.07727791		0	0.9152908		
RON	200	182.4722	91.20	200	183.1418	91.60	
ANTHANUM	0	-0.008883124		0	-0.008419473		
EAD	0	-0.02885473		1	0.8757265	87.60	
ITHIUM	0	0.005254951		0	0.00377048		
MAGNESIUM	500	445.6935	89.10	500	446.0002	89.20	
MANGANESE	0	0.004292363		0.50	0.508835	102	
MOLYBDENUM	0	0.001307683		0.50	0.5198888	104	
NICKEL	0	-0.001906144		1	0.9211901	92.10	
PHOSPHORUS	0	0.01053435		0	0.0091215		
POTASSIUM	0	-0.09170468		0	-0.07259864		
SELENIUM	0	0.02223213		0.50	0.5161625	103	
SILICON	0	0.0202869		1	1.094529	109	
SILVER	0	0.0001814243		1	1.161678	116	
SODIUM	0	0.1001602		0	0.08107117		
STRONTIUM	0	0.004067084		0	0.004128314		
SULFUR	0	-0.05367699		0	-0.07892034		
THALLIUM	0	-0.01282431		0.50	0.4551179	91	
ΓIN	0	-0.01341143		0.50	0.430177	86	
ΓΙΤΑΝΙUΜ	0	0.006659427		0.50	0.5121024	102	
/ANADIUM	0	0.001032534		0.50	0.48235	96.50	
ZINC	0	0.005763101		1	0.833053	83.30	

ICSA Limits: 80 - 120

ICSAB Limits: 80 - 120

ACCOUNT: Cardno - Peachtree Corners, GA PROJECT: CHIL0Q120 SDG: L1393214 DATE/TIME: 08/27/2114:22

PAGE: 21 of 35

5A-IN

MATRIX SPIKE / MATRIX SPIKE DUPLICATE RECOVERY L1393214-01,02

SAMPLE NO.: R3697192-4 R3697192-5

MS Sample / File ID: MSD Sample / File ID: OS Sample / File ID: Instrument ID:	MSD Sample / File ID: R3697192-5 / 20210827013654			A	SDG: Analytical Batch: Matrix:			L1393214 WG1729585 Waste		
Analytical Method:	6010D									
Analyte	Spike Amount	OS Result	MS Result	MSD Result	MS Rec.	MSD Rec.	Dilution	Rec. Limits	RPD	RPD Limits
	mg/l	mg/l	mg/l	mg/l	%	%		%	%	%
Lead	10.0	ND	9.83	9.86	98.3	98.6	1	75.0 - 125	0.373	20

*: Value outside the established quality control limits.

D: Surrogate recovery cannot be used for control limit evaluation due to dilution.

ACCOUNT:	PROJECT:	SDG:	DATE/TIME:	PAGE:
Cardno - Peachtree Corners, GA	CHIL0Q120	L1393214	08/27/2114:22	22 of 35

LABORATORY CONTROL SAMPLE LABORATORY CONTROL SAMPLE DUPLICATE RECOVERY L1393214-01,02

SAMPLE NO.: R3697192-2

LCSI Instr	iD Sample / File ID:				A	SDG: Analytical Batch: Dilution Factor: Matrix:		L1393214 WG1729585 1		
And	Analyte	00100	Spike Amount	LCS Result	LCSD Result	LCS Rec.		Rec. Limits	Waste RPD	RPD Limits
			mg/l	mg/l		%	%	%	%	%
	Lead		10.0	9.77		97.7		80.0 - 120		

*: Value outside the established quality control limits.

D: Surrogate recovery cannot be used for control limit evaluation due to dilution.

ACCOUNT:	PROJECT:	SDG:	DATE/TIME:	PAGE:
Cardno - Peachtree Corners, GA	CHILOQ120	L1393214	08/27/2114:22	23 of 35

ICP AND ICP/MS SERIAL DILUTIONS L1393214-01,02

	Analyte	OS Result	SD Result	RPD	RPD Limits	
Analytical Method:	6010D					
Instrument ID:	ICP12		Matrix:			Waste
Lab File ID:	20210827013201		Dilutio	n Factor:		5
OS Sample / File ID:	L1393142-01 / 20210827012909		Analyti	cal Batch:		WG1729585
SD Sample / File ID:	R3697192-3 / 20210827013201		SDG:			L1393214

mg/l

ND

%

0.000

mg/l

ND

%

10

*: Value outside the established quality control limits.

D: Surrogate recovery cannot be used for control limit evaluation due to dilution.

Lead

ACCOUNT:	PROJECT:	SDG:	DATE/TIME:	PAGE:
Cardno - Peachtree Corners, GA	CHILOQ120	L1393214	08/27/21 14:22	24 of 35

DETECTION LIMIT SUMMARY

Lab : Matr	Sample IDs: ix:	L1393214-01,02 Waste			Analytical Method: Prep Method:	6010E 3015	6010D 3015		
	Analyte		CAS Wavelength		Mass	MDL mg/l	RDL mg/l		
	Lead		7439-92-1	189.0420	220.3530	0.0330	0.10		

SDG: L1393214 DATE/TIME: 08/27/21 14:22

10A-IN

INTERELEMENT CORRECTION FACTORS

SDG:		L1393214		Analytica	al Method:	60	010D	
Instrumen	t ID:	ICP12		Date:		80		
Analyte	Wavelength	ARSENIC	CALCIUM	CHROMIUM	COBALT	COPPER	IRON	LANTHANUM
	nm	189.0420	317.9330	267.7160	228.6160	324.7540	259.94	333.7490
ALUMINUM	308.2150							
ANTIMONY	206.8330			-0.00010364				
ARSENIC	189.0420							-0.00520043
BARIUM	233.5270						-0.00011317	
BERYLLIUM	313.0420							
CADMIUM	228.8020	-0.25019590						
CHROMIUM	267.7160							
COBALT	228.6160							
IRON	271.4410				-0.00018664			
LEAD	220.3530					-0.00003085		-0.00013179
LITHIUM	670.7840		-0.00032182					
SELENIUM	196.09			-0.00001854				
THALLIUM	190.8560				-0.00026544			

SDG: L1393214 DATE/TIME: 08/27/2114:22

10A-IN

INTERELEMENT CORRECTION FACTORS

DG:	L1393	214		Analytical Method	4:	6010D		
strument ID:	ICP12			Date:		08/24/21 13:38		
Analyte	Wavelength	MANGANESE	SILICON	TIN	TITANIUM	VANADIUM		
	nm	257.61	251.6110	189.9890	334.9410	292.4020		
ALUMINUM	308.2150					-0.00434031		
ANTIMONY	206.8330			-0.00419814				
ARSENIC	189.0420							
BARIUM	233.5270							
BERYLLIUM	313.0420					-0.02889282		
CADMIUM	228.8020							
CHROMIUM	267.7160	-0.00003148						
COBALT	228.6160				-0.00101627			
IRON	271.4410							
LEAD	220.3530		-0.00008881					
LITHIUM	670.7840							
SELENIUM	196.09							
THALLIUM	190.8560	-0.00000492						

SDG: L1393214 DATE/TIME: 08/27/2114:22

LINEAR DYNAMIC RANGE

SDG: Instrument ID:	L1393214 ICP12		Analytical Method: Date:						
instrument ID:		Date:		06/16/21 08:38					
		Analyte	LDR						
			ppm						
		ALUMINUM	500	-					
		ANTIMONY	10						
		ARSENIC	50						
		BARIUM	50						
		BERYLLIUM	10						
		BORON	50						
		CADMIUM	10						
		CALCIUM	1000						
		CHROMIUM	50						
		COBALT	50						
		COPPER	50						
		IRON	500						
		LEAD	100						
		LITHIUM	10						
		MAGNESIUM	1000						
		MANGANESE	20						
		MOLYBDENUM	20						
		NICKEL	50						
		PHOSPHORUS	200						
		POTASSIUM	500						
		SELENIUM	10						
		SILICON	40						
		SILVER	10						
		SODIUM	1000						
		STRONTIUM	20						
		SULFUR	200						
		THALLIUM	10						
		TIN	50						
		TITANIUM	50						
		VANADIUM	20						
		ZINC	20						

SDG: L1393214 DATE/TIME: 08/27/21 14:22

ANALYSIS LOG

SDG:	L1393214	Analytical Meth	od:	6010D				
Instrument ID:	ICP12	Calibration Star		08/26/21 16:03				
Analytical Run:	082621ICP12	Calibration End	Date:	08/26/21 16:20				
Client Sample ID	Lab Sample ID	File ID	Analysis Date Time	Dilution	Batch			
CALBLK	ICP120826211601	20210826160102	08/26/21 16:01					
CAL	STD1	20210826160349	08/26/21 16:03					
CAL	STD2	20210826160620	08/26/21 16:06					
CAL	STD3	20210826160846	08/26/21 16:08					
CAL	STD4	20210826161118	08/26/21 16:11					
CAL	STD5	20210826161357	08/26/21 16:13					
CAL	STD6	20210826161653	08/26/21 16:16					
CAL	STD7	20210826162006	08/26/21 16:20					
ICV	ICP120826211623-2	20210826162302-2	08/26/21 16:23					
ICB	ICP120826211625-2	20210826162546-2	08/26/21 16:25					
CVLL	ICP120826211633-2	20210826163341-2	08/26/21 16:33					
CSA	ICP120826211642-2	20210826164235-2	08/26/21 16:42					
CSAB	ICP120826211645-2	20210826164528-2	08/26/21 16:45					
CSA	ICP120826212324-2	20210826232404-2	08/26/21 23:24					
ICSAB	ICP120826212326-2	20210826232657-2	08/26/21 23:26					
CCV	ICP120827210111-2	20210827011107-2	08/27/21 01:11					
ССВ	ICP120827210113-2	20210827011358-2	08/27/21 01:13					
CCV	ICP120827210118-2	20210827011817-2	08/27/21 01:18					
ССВ	ICP120827210121-2	20210827012110-2	08/27/21 01:21					
BLANK	R3697192-1	20210827012400	08/27/21 01:24	1	WG1729585			
LCS	R3697192-2	20210827012625	08/27/21 01:26	1	WG1729585			
OS	L1393142-01	20210827012909	08/27/21 01:29					
_1393142-01	L1393142-01	20210827012909	08/27/21 01:29	1	WG1729585			
SD	R3697192-3	20210827013201	08/27/21 01:32	5	WG1729585			
MS	R3697192-4	20210827013429	08/27/21 01:34	1	WG1729585			
MSD	R3697192-5	20210827013654	08/27/21 01:36	1	WG1729585			
CCV	ICP120827210150-2	20210827015003-2	08/27/21 01:50					
ССВ	ICP120827210152-2	20210827015256-2	08/27/21 01:52					
RP-01	L1393214-01	20210827020335	08/27/21 02:03	1	WG1729585			
RP-02	L1393214-02	20210827020616	08/27/21 02:06	1	WG1729585			
CCV	ICP120827210211	20210827021127	08/27/21 02:11					
ССВ	ICP120827210214	20210827021417	08/27/21 02:14					
CSA	ICP120827210504-2	20210827050442-2	08/27/21 05:04					
ICSAB	ICP120827210507-2	20210827050738-2	08/27/21 05:07					
CCVLL	ICP120827210852-2	20210827085229-2	08/27/21 08:52					

SDG: L1393214 DATE/TIME: 08/27/2114:22

INITIAL CALIBRATION RECOVERY

SDG: Instrument ID: Analytical Method:	L1393214 ICP12 6010D			Calibration (begin) date Calibration (end) date/ Analytical Run:		08/26/21 16:0 08/26/21 16:2 082621ICP12	0
Analyte		Std Conc mg/l	Result mg/l	Rec. %	Std Conc mg/l	Result mg/l	Rec. %
LEAD File ID:		0.0050	.005706251 202108261603	114 349	0.50	.5014866 20210826160620	100 0

PROJECT: CHILOQ120 SDG: L1393214 DATE/TIME: 08/27/2114:22

PAGE: 30 of 35

INITIAL CALIBRATION RECOVERY

SDG: Instrument ID: Analytical Method:	L1393214 ICP12 6010D		с	Calibration (begin) dat Calibration (end) date/ Analytical Run:	08/26/21 16:03 08/26/21 16:20 082621ICP12		
Analyte		Std Conc	Result	Rec.	Std Conc	Result	Rec.
		mg/l	mg/l	%	mg/l	mg/l	%
LEAD		1	.9953524	99.50	2	2.00195	100
File ID:			2021082616084	6		20210826161118	

SDG: L1393214 DATE/TIME: 08/27/2114:22

16A-IN				ITIAL BRATION					
SDG:		L1393214	Calibration (begin) date/time: Calibration (end) date/time:				08/26/21 16:03		
Instrume		ICP12			. ,	9:	08/26/21 16:20		
Analytica	al Method:	6010D		Analytica	Run:		082621ICP12		
	Analyte		Wavelength	Cal. Type	Weightage	Corr.	Slope	Incpt	
	LEAD		220.353	8	5	0.999995	814.8551	3.229964	

Calibration Type

8 = Linear Regression Forced through Blank

Weightage

5 = None

ACCOUNT: Cardno - Peachtree Corners, GA PROJECT: CHIL0Q120 SDG: L1393214

ם 20

DATE/TIME: 08/27/2114:22 PAGE: 32 of 35

GLOSSARY OF TERMS

Guide to Reading and Understanding Your Laboratory Report

The information below is designed to better explain the various terms used in your report of analytical results from the Laboratory. This is not intended as a comprehensive explanation, and if you have additional questions please contact your project representative.

Results Disclaimer - Information that may be provided by the customer, and contained within this report, include Permit Limits, Project Name, Sample ID, Sample Matrix, Sample Preservation, Field Blanks, Field Spikes, Field Duplicates, On-Site Data, Sampling Collection Dates/Times, and Sampling Location. Results relate to the accuracy of this information provided, and as the samples are received.

Abbreviations and Definitions

Corr.	Correlation Coefficient.
Incpt	Intercept.
Mass	Mass of parameter.
MDL	Method Detection Limit.
RDL	Reported Detection Limit.
Rec.	Recovery.
RPD	Relative Percent Difference.
SDG	Sample Delivery Group.
Analyte	The name of the particular compound or analysis performed. Some Analyses and Methods will have multiple analytes reported.
Dilution	If the sample matrix contains an interfering material, the sample preparation volume or weight values differ from the standard, or if concentrations of analytes in the sample are higher than the highest limit of concentration that the laboratory can accurately report, the sample may be diluted for analysis. If a value different than 1 is used in this field, the result reported has already been corrected for this factor.
Limits	These are the target % recovery ranges or % difference value that the laboratory has historically determined as normal for the method and analyte being reported. Successful QC Sample analysis will target all analytes recovered or duplicated within these ranges.
Qualifier	This column provides a letter and/or number designation that corresponds to additional information concerning the result reported. If a Qualifier is present, a definition per Qualifier is provided within the Glossary and Definitions page and potentially a discussion of possible implications of the Qualifier in the Case Narrative if applicable.
Result	The actual analytical final result (corrected for any sample specific characteristics) reported for your sample. If there was no measurable result returned for a specific analyte, the result in this column may state "ND" (Not Detected) or "BDL" (Below Detectable Levels). The information in the results column should always be accompanied by either an MDL (Method Detection Limit) or RDL (Reporting Detection Limit) that defines the lowest value that the laboratory could detect or report for this analyte.
Slope	Slope of calibration curve.
Uncertainty (Radiochemistry)	Confidence level of 2 sigma.
Wavelength	Wavelength of parameter.
Case Narrative (Cn)	A brief discussion about the included sample results, including a discussion of any non-conformances to protocol observed either at sample receipt by the laboratory from the field or during the analytical process. If present, there will be a section in the Case Narrative to discuss the meaning of any data qualifiers used in the report.
Quality Control Summary (Qc)	This section of the report includes the results of the laboratory quality control analyses required by procedure or analytical methods to assist in evaluating the validity of the results reported for your samples. These analyses are not being performed on your samples typically, but on laboratory generated material.
Sample Chain of Custody (Sc)	This is the document created in the field when your samples were initially collected. This is used to verify the time and date of collection, the person collecting the samples, and the analyses that the laboratory is requested to perform. This chain of custody also documents all persons (excluding commercial shippers) that have had control or possession of the samples from the time of collection until delivery to the laboratory for analysis.
Sample Results (Sr)	This section of your report will provide the results of all testing performed on your samples. These results are provided by sample ID and are separated by the analyses performed on each sample. The header line of each analysis section for each sample will provide the name and method number for the analysis reported.
Sample Summary (Ss)	This section of the Analytical Report defines the specific analyses performed for each sample ID, including the dates and times of preparation and/or analysis.
Qualifier	Description

The remainder of this page intentionally left blank, there are no qualifiers applied to this SDG.

SDG: L1393214 Τс

Ss

Cn

Su

ίGΓ

AI

Sc

ACCREDITATIONS & LOCATIONS

Pace Analytical National 12065 Lebanon Rd Mount Juliet, TN 37122

Alabama	40660	Nebraska	NE-OS-15-05
Alaska	17-026	Nevada	TN000032021-1
Arizona	AZ0612	New Hampshire	2975
Arkansas	88-0469	New Jersey–NELAP	TN002
California	2932	New Mexico ¹	TN00003
Colorado	TN00003	New York	11742
Connecticut	PH-0197	North Carolina	Env375
Florida	E87487	North Carolina ¹	DW21704
Georgia	NELAP	North Carolina ³	41
Georgia ¹	923	North Dakota	R-140
Idaho	TN00003	Ohio–VAP	CL0069
Illinois	200008	Oklahoma	9915
Indiana	C-TN-01	Oregon	TN200002
lowa	364	Pennsylvania	68-02979
Kansas	E-10277	Rhode Island	LAO00356
Kentucky ¹⁶	KY90010	South Carolina	84004002
Kentucky ²	16	South Dakota	n/a
Louisiana	AI30792	Tennessee ¹⁴	2006
Louisiana	LA018	Texas	T104704245-20-18
Maine	TN00003	Texas ⁵	LAB0152
Maryland	324	Utah	TN000032021-11
Massachusetts	M-TN003	Vermont	VT2006
Michigan	9958	Virginia	110033
Minnesota	047-999-395	Washington	C847
Mississippi	TN00003	West Virginia	233
Missouri	340	Wisconsin	998093910
Montana	CERT0086	Wyoming	A2LA
A2LA – ISO 17025	1461.01	AIHA-LAP,LLC EMLAP	100789
A2LA – ISO 17025 ⁵	1461.02	DOD	1461.01
Canada	1461.01	USDA	P330-15-00234
EPA–Crypto	TN00003		

¹ Drinking Water ² Underground Storage Tanks ³ Aquatic Toxicity ⁴ Chemical/Microbiological ⁵ Mold ⁶ Wastewater n/a Accreditation not applicable

* Not all certifications held by the laboratory are applicable to the results reported in the attached report.

* Accreditation is only applicable to the test methods specified on each scope of accreditation held by Pace Analytical.

SDG: L1393214 DATE/TIME: 08/27/2114:32 Τс

Ss

Cn

Su

GI

Sc

			formation:						Anal	ysis / Conta	iner / Pres	ervative		Chain of Custody	Page of
		Ashte Gent -vore	on Smit Boy Circle iross, GA	hwive 2 stez: 30071	20	Pres Chk								- Pace National Co	Analytical*
Report to: <u>A. Snithusick</u> Project Description: <u>Citv/State</u>			inn. Smith	wicke	Ceusina, L	sm								12065 Lebanon Rd Mount Juliet, TN 37 Phone: 615-758-58	
Project Description:		City/State Collected:	Chiloguir	1,0R	Please (PT MT	Circle: CT ET								Phone: 800-767-58 Fax: 615-758-5859	
Phone:	Client Project #	2120	Lab Projec	:t#										SDG # C2	139 3214
Collected by (print): A-Smithurite	Site/Facility ID #		P.O. #											Acctnum:	
Collected by (signature):	Rush? (Lab Mil Same Day Two Day Two Day Three Day		Quote #	e Results N	eeded	No	d Tch?							Template: Prelogin: PM: PB:	
Sample ID	Comp/Grab	Matrix*	Depth	Date	Time	Cntrs	Lee							Shipped Via: Remarks	Sample # (lab only)
RP-01	ComP		8	5.18.21		ι	X		1			1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1		TUP	-01
RP-02	12			L	- 1 46-2		X							TCL?	-02
<u>i and and and and and and and and and and</u>									1 AL						
				-		di.									
and the second s												10.0			
Matrix: S - Soil AIR - Air F - Filter W - Groundwater B - Bioassay W - WasteWater W - Drinking Water T - Other	Remarks: Samples returned via UPS FedEx			Trackin	g# 5		74	436		рн Flow Э 6	Temp Other _		COC Sea COC Sign Bottles Correct Sufficie	Sample Receipt CM 1 Present/Intact ned/Accurate: arrive intact: bottles used: bottles used: ent volume sent: <u>If Applicab</u> o Headspace:	
elinquished by : (Signature)	And the second	5.18.21	Time: 16D	1	d by: (Signat	3			Trip	Blank Rece	НС	CL / MeoH	Preserva RAD Scre	ation Correct/Ch een <0.5 mR/hr:	ecked: _Y _N
élinquished by : (Signature)	Date	:	Time:	19	d by: (Signat				Ten	Biot	C Bottles	Received:	If preserv	vation required by Log	gin: Date/Time
elinquished by : (Signature)	Date	:	Time:	Receive	d for ab by:	(Signat	ure)		Pate	KIU	Time	7:00	Hold:	The second	Condition: NCF / OK

Appendix C Inspector Accreditations





Greenville Technical College

PQ ... PQ

PO Box 5616, 738 S. Pleasantburg Drive, Greenville, South Carolina 29606-5616 (864) 250-8800

ROBERT HALL

307 Block House Rd., Greenville, SC 29615

2999

has completed the requisite training for asbestos accreditation under TSCA Title II and has met the requirements of and passed the examination for an EPA approved

Asbestos Project Designer Refresher **Training Course**

222 - EVT514 - 003

Certificate Number

January 12, 2022

Course Date(s)

January 12, 2022

Examination Date Attended and Satisfactorily Completed Course Exam with a Passing Score of 70% or Better

Greenville, SC

reenvi **Technical** College **Economic Development** and Corporate Training

Mike Cashio, Principal Instructor

ch. Training Manager

January 12, 2023

Expiration Date Approved for Remote Delivery

The Environmental Institute
William Smithwick
Social Security Number - XXX-XX-1496 Cardno - 6611 Bay Circle, Suite 220, Norcross, GA 30071
Has completed 4 hours of coursework and satisfactorily passed an examination that meets all criteria required for EPA/AHERA/ASHARA (TSCA Title II) Approved Reaccreditation
Asbestos in Buildings: Inspector Refresher
November 19, 2020 Course Date <u>18209</u> Certificate Number
November 19, 2020 Examination Date November 18, 2021 Expiration Date Amage: A construction of the structor Thomas G. Laupenthal Principal Instructor David W. Hogue - Training Manager
(Approved by the ABIH Certification Maintenance Committee for 1/2 CM point - Approval #11-577) (Florida Provider Registration Number FL49-0001342 - Course #FL49-0002805) TEI - 1395 S. Marietta Parkway SE - Building 100, Suite 124 - Marietta, GA 30067 Phone: 770-427-3600 - Website: www.tei-atl.com

The Environmental Institute

William Smithwick

Social Security Number - XXX-XX-1496 Cardno - 2010 Druid Hills Reserve Drive NE - Atlanta, Georgia 30329

Has completed 24 hours of coursework and satisfactorily passed the hands-on skills assessment and an examination that meets training criteria in accordance with requirements for Lead-Based Paint Activities in Target Housing and Child-Occupied Facilities as regulated by Georgia DNR/EPD Chapter 391-3-24 and U. S. EPA TSCA 40 CFR Part 745 for the initial course titled

Lead Inspector: EPA (Target Housing & Child-Occupied Facilities)

February 24-26, 2020

February 26, 2020

August 26, 2020 EPA Interim Expiration Date

February 25, 2022 Georgia Expiration Date

February 25, 2023 EPA Expiration Date David W. Hogue - Principal Instructor / Training Manager



5300 Certificate Number

(Approved by the ABIH Certification Maintenance Committee for 3 CM points - Approval #11-563) TEI - 1395 S. Marietta Parkway SE - Building 100, Suite 124 - Marietta, GA 30067 Phone: 770-427-3600 - Website: www.tei-atl.com (State of Georgia Accredited - Certification No. 20-0799-006I - January 15, 1997)